ภาคผนวก ค

ใบรายงานผลวิเคราะห์

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23127986
Date Received : Nov 29, 2023
Date Reported : Dec 07, 2023
Report Number : 2823006-1

Sample Number	23127986-1
Sampled Date	Nov 23, 2023
Sample Description	Air Quality
Location	ที่จอดรถยนต์ภายนอกอาคาร (GPS 47N 0422851, 883964)
Date Analysis Commenced	Nov 30, 2023
Condition of Sample	Drawn into one glass filter paper (8x10 inch) placed in plastic bag and one quartz filter paper (8x10 inch) placed in plastic bag
Barometric Pressure	754 mmHg
Atmospheric Temperature	29.0 °C

Analyte	Sampled Date/time	Unit	LOD	LOQ (LOR)	Result	Guideline Limit	Method	Guideline	Testing Location
Air Testing									
Particulate matter as PM 10	23/11/23 - 24/11/23	mg/m3	-	0.005	0.024	0.12	In - house method : STM 04-052 based on U.S. Environmental Protection Agency 40 CFR, method 50, Appendix J, revised as of July 1, 2008 (Include sampling)	NEB No.24	Bangkok
Total Suspended Particulate	23/11/23 - 24/11/23	mg/m3	-	0.005	0.122	0.33	In - house method : STM 04-051 based on U.S. Environmental Protection Agency 40 CFR, method 50, Appendix B, revised as of July 1, 2008 (Include sampling)	NEB No.24	Bangkok

Guideline :
NEB No.24 : Notification of the National Environmental Board. No.24, 2004 (B.E.2547) dated September 22, 2004
Sampled By : Apiwat Chanta

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by
Orawan Rakyong
Scientist (3)

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23127975
Date Received : Nov 29, 2023
Date Reported : Dec 04, 2023
Report Number: 2822981-1

Sample Description	Air Quality
Location	ที่จอดรถยนต์ภายนอกอาคาร (GPS 47N 0422851, 883964)
Parameter	Carbon monoxide (ppm)
Measurement Date	Nov 23, 2023 - Nov 24, 2023
Measurement by	Apiwat Chanta

Time	23127975-1 Nov 23, 2023	-	-	-	-	-	-
10:00 AM - 11:00 AM	0.8	-	-	-	-	-	-
11:00 AM - 12:00 PM	0.8	-	-	-	-	-	-
12:00 PM - 01:00 PM	0.5	-	-	-	-	-	-
01:00 PM - 02:00 PM	0.3	-	-	-	-	-	-
02:00 PM - 03:00 PM	0.3	-	-	-	-	-	-
03:00 PM - 04:00 PM	0.3	-	-	-	-	-	-
04:00 PM - 05:00 PM	0.3	-	-	-	-	-	-
05:00 PM - 06:00 PM	0.3	-	-	-	-	-	-
06:00 PM - 07:00 PM	0.4	-	-	-	-	-	-
07:00 PM - 08:00 PM	0.5	-	-	-	-	-	-
08:00 PM - 09:00 PM	0.5	-	-	-	-	-	-
09:00 PM - 10:00 PM	0.5	-	-	-	-	-	-
10:00 PM - 11:00 PM	0.4	-	-	-	-	-	-
11:00 PM - 12:00 AM	0.4	-	-	-	-	-	-
12:00 AM - 01:00 AM	0.3	-	-	-	-	-	-
01:00 AM - 02:00 AM	0.2	-	-	-	-	-	-
02:00 AM - 03:00 AM	0.2	-	-	-	-	-	-
03:00 AM - 04:00 AM	0.1	-	-	-	-	-	-
04:00 AM - 05:00 AM	0.1	-	-	-	-	-	-
05:00 AM - 06:00 AM	0.2	-	-	-	-	-	-
06:00 AM - 07:00 AM	0.2	-	-	-	-	-	-
07:00 AM - 08:00 AM	0.3	-	-	-	-	-	-
08:00 AM - 09:00 AM	0.3	-	-	-	-	-	-
09:00 AM - 10:00 AM	0.4	-	-	-	-	-	-
Average	0.4	-	-	-	-	-	-
1hr - Maximum	0.8	-	-	-	-	-	-
Standard 1hr - Average	30	-	-	-	-	-	-

Standard : Notification of the National Environmental Board. No.10, 1995 (B.E.2538).
Reference Method : EPA 40 CFR Part 50Appendix C

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Orawan Rakyong
Scientist (3)

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23127976
Date Received : Nov 29, 2023
Date Reported : Dec 04, 2023
Report Number: 2822995-1

Sample Description	Air Quality
Location	ที่จอดรถยนต์ภายนอกอาคาร (GPS 47N 0422851, 883964)
Parameter	Nitrogen dioxide (ppm)
Measurement Date	Nov 23, 2023 - Nov 24, 2023
Measurement by	Apiwat Chanta

Time	23127976-1 Nov 23, 2023	-	-	-	-	-	-
10:00 AM - 11:00 AM	0.004	-	-	-	-	-	-
11:00 AM - 12:00 PM	0.009	-	-	-	-	-	-
12:00 PM - 01:00 PM	0.014	-	-	-	-	-	-
01:00 PM - 02:00 PM	0.013	-	-	-	-	-	-
02:00 PM - 03:00 PM	0.005	-	-	-	-	-	-
03:00 PM - 04:00 PM	0.006	-	-	-	-	-	-
04:00 PM - 05:00 PM	0.024	-	-	-	-	-	-
05:00 PM - 06:00 PM	0.020	-	-	-	-	-	-
06:00 PM - 07:00 PM	0.036	-	-	-	-	-	-
07:00 PM - 08:00 PM	0.031	-	-	-	-	-	-
08:00 PM - 09:00 PM	0.024	-	-	-	-	-	-
09:00 PM - 10:00 PM	0.030	-	-	-	-	-	-
10:00 PM - 11:00 PM	0.012	-	-	-	-	-	-
11:00 PM - 12:00 AM	0.011	-	-	-	-	-	-
12:00 AM - 01:00 AM	0.004	-	-	-	-	-	-
01:00 AM - 02:00 AM	0.006	-	-	-	-	-	-
02:00 AM - 03:00 AM	0.004	-	-	-	-	-	-
03:00 AM - 04:00 AM	0.001	-	-	-	-	-	-
04:00 AM - 05:00 AM	0.001	-	-	-	-	-	-
05:00 AM - 06:00 AM	0.002	-	-	-	-	-	-
06:00 AM - 07:00 AM	0.002	-	-	-	-	-	-
07:00 AM - 08:00 AM	0.006	-	-	-	-	-	-
08:00 AM - 09:00 AM	0.018	-	-	-	-	-	-
09:00 AM - 10:00 AM	0.035	-	-	-	-	-	-
Average	0.013	-	-	-	-	-	-
1hr - Maximum	0.036	-	-	-	-	-	-
Standard 1hr - Average	0.170	-	-	-	-	-	-

Standard : Notification of the National Environment Board No. 33, 2009 (B.E. 2552).
Reference Method : US EPAMethod Part 50 App. F (Chemiluminescence)

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Orawan Rakyong
Scientist (3)

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23127983
Date Received : Nov 29, 2023
Date Reported : Dec 04, 2023
Report Number: 2823000-1

Sample Description	Air Quality
Location	ที่จอดรถยนต์ภายนอกอาคาร (GPS 47N 0422851, 883964)
Parameter	Sulfur Dioxide (ppm)
Measurement Date	Nov 23, 2023 - Nov 24, 2023
Measurement by	Apiwat Chanta

Time	23127983-1 Nov 23, 2023	-	-	-	-	-	-
10:00 AM - 11:00 AM	<0.001	-	-	-	-	-	-
11:00 AM - 12:00 PM	0.001	-	-	-	-	-	-
12:00 PM - 01:00 PM	0.001	-	-	-	-	-	-
01:00 PM - 02:00 PM	<0.001	-	-	-	-	-	-
02:00 PM - 03:00 PM	<0.001	-	-	-	-	-	-
03:00 PM - 04:00 PM	<0.001	-	-	-	-	-	-
04:00 PM - 05:00 PM	<0.001	-	-	-	-	-	-
05:00 PM - 06:00 PM	<0.001	-	-	-	-	-	-
06:00 PM - 07:00 PM	<0.001	-	-	-	-	-	-
07:00 PM - 08:00 PM	<0.001	-	-	-	-	-	-
08:00 PM - 09:00 PM	<0.001	-	-	-	-	-	-
09:00 PM - 10:00 PM	<0.001	-	-	-	-	-	-
10:00 PM - 11:00 PM	<0.001	-	-	-	-	-	-
11:00 PM - 12:00 AM	<0.001	-	-	-	-	-	-
12:00 AM - 01:00 AM	<0.001	-	-	-	-	-	-
01:00 AM - 02:00 AM	<0.001	-	-	-	-	-	-
02:00 AM - 03:00 AM	<0.001	-	-	-	-	-	-
03:00 AM - 04:00 AM	<0.001	-	-	-	-	-	-
04:00 AM - 05:00 AM	<0.001	-	-	-	-	-	-
05:00 AM - 06:00 AM	<0.001	-	-	-	-	-	-
06:00 AM - 07:00 AM	<0.001	-	-	-	-	-	-
07:00 AM - 08:00 AM	<0.001	-	-	-	-	-	-
08:00 AM - 09:00 AM	<0.001	-	-	-	-	-	-
09:00 AM - 10:00 AM	<0.001	-	-	-	-	-	-
Average	<0.001	-	-	-	-	-	-
1hr - Maximum	0.001	-	-	-	-	-	-
Standard 1hr - Average	0.3	-	-	-	-	-	-
Standard 24 hrs - Average	0.12	-	-	-	-	-	-

Standard : Notification of the National Environment Board No.10, 1995 (B.E.2538), No. 21, 2001 (B.E.2544) and No.24, 2004 (B.E.2547).
Reference Method : US EPA Method Part 53 and 58

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Orawan Rakyong
Scientist (3)

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23127984
Date Received : Nov 29, 2023
Date Reported : Dec 11, 2023
Report Number: 2823003-1

Sample Description	Air Quality
Location	ที่จอดรถยนต์ภายนอกอาคาร (GPS 47N 0422851, 883964)
Parameter	Total Hydrocarbon (ppm)
Measurement Date	Nov 23, 2023 - Nov 24, 2023
Measurement by	Apiwat Chanta

Time	23127984-1 Nov 23, 2023	-	-	-	-	-	-
10:00 AM - 11:00 AM	2.56	-	-	-	-	-	-
11:00 AM - 12:00 PM	2.45	-	-	-	-	-	-
12:00 PM - 01:00 PM	2.60	-	-	-	-	-	-
01:00 PM - 02:00 PM	2.48	-	-	-	-	-	-
02:00 PM - 03:00 PM	2.41	-	-	-	-	-	-
03:00 PM - 04:00 PM	2.42	-	-	-	-	-	-
04:00 PM - 05:00 PM	2.56	-	-	-	-	-	-
05:00 PM - 06:00 PM	2.49	-	-	-	-	-	-
06:00 PM - 07:00 PM	2.51	-	-	-	-	-	-
07:00 PM - 08:00 PM	2.84	-	-	-	-	-	-
08:00 PM - 09:00 PM	2.78	-	-	-	-	-	-
09:00 PM - 10:00 PM	2.66	-	-	-	-	-	-
10:00 PM - 11:00 PM	2.60	-	-	-	-	-	-
11:00 PM - 12:00 AM	2.59	-	-	-	-	-	-
12:00 AM - 01:00 AM	3.01	-	-	-	-	-	-
01:00 AM - 02:00 AM	2.44	-	-	-	-	-	-
02:00 AM - 03:00 AM	2.49	-	-	-	-	-	-
03:00 AM - 04:00 AM	2.35	-	-	-	-	-	-
04:00 AM - 05:00 AM	2.40	-	-	-	-	-	-
05:00 AM - 06:00 AM	2.45	-	-	-	-	-	-
06:00 AM - 07:00 AM	2.60	-	-	-	-	-	-
07:00 AM - 08:00 AM	2.63	-	-	-	-	-	-
08:00 AM - 09:00 AM	2.55	-	-	-	-	-	-
09:00 AM - 10:00 AM	2.47	-	-	-	-	-	-
Average	2.56	-	-	-	-	-	-
1hr - Maximum	3.01	-	-	-	-	-	-

Reference Method : Total Hydrocarbon Analyzer (FID)

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Orawan Rakyong
Scientist (3)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736403-1

Sample Number	2371803-5
Sampled Date	Jul 24, 2023 1:50 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	7900000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	146	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	98	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.6	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	4.5	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	1.2	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	396	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	62.2	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736403-1

Sample Number	2371803-5
Sampled Date	Jul 24, 2023 1:50 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	142	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารละลายได้ทั้งหมดในน้ำใช้ = 96 mg/L

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736404-1

Sample Number	2371803-6
Sampled Date	Jul 24, 2023 1:40 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	1100000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	24.3	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	3	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.6	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	<0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	0.8	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	376	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	52.9	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736404-1

Sample Number	2371803-6
Sampled Date	Jul 24, 2023 1:40 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	45	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารละลายได้ทั้งหมดในน้ำใช้ = 96 mg/L

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736405-1

Sample Number	2371803-7
Sampled Date	Jul 24, 2023 1:55 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	790000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	363	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	36	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	6.8	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	5.5	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	6.4	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	420	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	58.0	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736405-1

Sample Number	2371803-7
Sampled Date	Jul 24, 2023 1:55 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	280	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารละลายได้ทั้งหมดในน้ำใช้ = 96 mg/L

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736406-1

Sample Number	2371803-8
Sampled Date	Jul 24, 2023 1:45 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	49000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	17.9	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	<3	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.0	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	4.8	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	372	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	52.3	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736406-1

Sample Number	2371803-8
Sampled Date	Jul 24, 2023 1:45 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	15	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารละลายได้ทั้งหมดในน้ำใช้ = 96 mg/L

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736407-1

Sample Number	2371803-9
Sampled Date	Jul 24, 2023 1:05 PM
Sample Description	น้ำใช้
Location	น้ำใช้ภายในโรงแรม
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in one plastic bottle, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Dissolved solids Dried at 180 degree C	mg/L	-	5	96	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla

Guideline :

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769825-1

Sample Number	2391738-9
Sampled Date	Aug 28, 2023 3:15 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	4900000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	182	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	23	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.5	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	4.0	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	1.0	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	292	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	65.9	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769825-1

Sample Number	2391738-9
Sampled Date	Aug 28, 2023 3:15 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	204	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769826-1

Sample Number	2391738-10
Sampled Date	Aug 28, 2023 3:00 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	2400000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	43.2	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	3	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.7	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	<0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	0.6	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	332	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	54.1	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769826-1

Sample Number	2391738-10
Sampled Date	Aug 28, 2023 3:00 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	64	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769827-1

Sample Number	2391738-11
Sampled Date	Aug 28, 2023 3:25 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	790000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	972	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	191	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	6.3	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	60.0	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	8.1	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	340	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	107	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769827-1

Sample Number	2391738-11
Sampled Date	Aug 28, 2023 3:25 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	1212	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769828-1

Sample Number	2391738-12
Sampled Date	Aug 28, 2023 2:45 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	240000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	29.9	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	3	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.1	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	3.0	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	264	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	44.9	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769828-1

Sample Number	2391738-12
Sampled Date	Aug 28, 2023 2:45 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	31	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769829-1

Sample Number	2391738-13
Sampled Date	Aug 28, 2023 2:00 PM
Sample Description	น้ำใช้
Location	น้ำใช้ภายในโรงแรม
Date Analysis Commenced	Aug 30, 2023
Condition of Sample	Contained in one plastic bottle, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Water Testing						
Total Dissolved solids Dried at 180 degree C	mg/L	-	5	87	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2398983
Date Received : Sep 26, 2023
Date Reported : Oct 05, 2023
Report Number : 2798360-1

Sample Number	2398983-5
Sampled Date	Sep 25, 2023 1:49 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Sep 26, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	4900000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	314	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	115	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.5	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	14.0	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	2.0	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	392	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	54.2	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2398983
Date Received : Sep 26, 2023
Date Reported : Oct 05, 2023
Report Number : 2798360-1

Sample Number	2398983-5
Sampled Date	Sep 25, 2023 1:49 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Sep 26, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	588	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2398983
Date Received : Sep 26, 2023
Date Reported : Oct 05, 2023
Report Number : 2798361-1

Sample Number	2398983-6
Sampled Date	Sep 25, 2023 1:30 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Sep 26, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	240000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	8.1	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	5	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.6	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	<0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	0.6	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	300	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	28.9	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2398983
Date Received : Sep 26, 2023
Date Reported : Oct 05, 2023
Report Number : 2798361-1

Sample Number	2398983-6
Sampled Date	Sep 25, 2023 1:30 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Sep 26, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	40	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2398983
Date Received : Sep 26, 2023
Date Reported : Oct 05, 2023
Report Number : 2798362-1

Sample Number	2398983-7
Sampled Date	Sep 25, 2023 2:02 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Sep 26, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	2400000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	1226	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	161	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	6.4	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	84.0	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	7.2	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	424	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	89.5	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2398983
Date Received : Sep 26, 2023
Date Reported : Oct 05, 2023
Report Number : 2798362-1

Sample Number	2398983-7
Sampled Date	Sep 25, 2023 2:02 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Sep 26, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	2120	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2398983
Date Received : Sep 26, 2023
Date Reported : Oct 05, 2023
Report Number : 2798363-1

Sample Number	2398983-8
Sampled Date	Sep 25, 2023 1:36 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Sep 26, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	330000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	46.4	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	7	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.2	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	<0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	4.4	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	316	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	42.6	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2398983
Date Received : Sep 26, 2023
Date Reported : Oct 05, 2023
Report Number : 2798363-1

Sample Number	2398983-8
Sampled Date	Sep 25, 2023 1:36 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Sep 26, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	20	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2398983
Date Received : Sep 26, 2023
Date Reported : Oct 05, 2023
Report Number : 2798364-1

Sample Number	2398983-9
Sampled Date	Sep 25, 2023 2:11 PM
Sample Description	น้ำใช้
Location	น้ำใช้ภายในโรงแรม
Date Analysis Commenced	Sep 26, 2023
Condition of Sample	Contained in one plastic bottle, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Water Testing						
Total Dissolved solids Dried at 180 degree C	mg/L	-	5	114	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822522-1

Sample Number	23113448-5
Sampled Date	Oct 26, 2023 2:30 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	3300000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	142	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	29	≤20	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.6	5.0-9.0	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	10.0	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	2.4	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	296	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	75.9	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822522-1

Sample Number	23113448-5
Sampled Date	Oct 26, 2023 2:30 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	256	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822523-1

Sample Number	23113448-6
Sampled Date	Oct 26, 2023 2:23 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	2400000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	81.9	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	9	≤20	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.6	5.0-9.0	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	<0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	1.2	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	284	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	64.8	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822523-1

Sample Number	23113448-6
Sampled Date	Oct 26, 2023 2:23 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	125	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822524-1

Sample Number	23113448-7
Sampled Date	Oct 26, 2023 2:40 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	24000000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	738	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	55	≤20	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	6.5	5.0-9.0	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	19.0	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	9.5	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	332	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	80.0	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822524-1

Sample Number	23113448-7
Sampled Date	Oct 26, 2023 2:40 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	1204	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822525-1

Sample Number	23113448-8
Sampled Date	Oct 26, 2023 2:27 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
[A] Fecal Coliform	MPN/100mL	-	-	2400000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Water Testing							
BOD *	mg/L	-	2	68.4	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	10	≤20	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	6.9	5.0-9.0	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	<0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	3.6	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	304	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	45.9	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822525-1

Sample Number	23113448-8
Sampled Date	Oct 26, 2023 2:27 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	34	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- [A] Analysis conducted by ALS Laboratory Group (Thailand) Co.,Ltd. Bangkok Branch, DSS Accreditation No. 0009.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

LABORATORY ACCREDITATION
BLA-DSS

TESTING
No.0166

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822526-1

Sample Number	23113448-9
Sampled Date	Oct 26, 2023 2:00 PM
Sample Description	น้ำใช้
Location	น้ำใช้ภายในโรงแรม
Date Analysis Commenced	Oct 30, 2023
Condition of Sample	Contained in one plastic bottle, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Water Testing						
Total Dissolved solids Dried at 180 degree C	mg/L	-	5	69	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta B.
Ananta Boonphet
Scientist (2)

LABORATORY ACCREDITATION
BLA-DSS

TESTING
No.0166

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851098-1

Sample Number	23121879-7
Sampled Date	Nov 23, 2023 2:50 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	1700000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Water Testing							
BOD *	mg/L	-	2	143	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	13	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.8	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	0.9	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	1.2	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	320	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	85.7	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta B.

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851098-1

Sample Number	23121879-7
Sampled Date	Nov 23, 2023 2:50 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	144	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารที่ละลายได้ทั้งหมดในน้ำใช้ = 81 มิลลิกรัมต่อลิตร

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851099-1

Sample Number	23121879-8
Sampled Date	Nov 23, 2023 2:38 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	1300000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Water Testing							
BOD *	mg/L	-	2	82.4	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	10	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.6	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	<0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	1.0	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	304	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	71.9	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851099-1

Sample Number	23121879-8
Sampled Date	Nov 23, 2023 2:38 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	104	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารที่ละลายได้ทั้งหมดในน้ำใช้ = 81 มิลลิกรัมต่อลิตร

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

LABORATORY ACCREDITATION
BLA-DSS

TESTING
No.0166

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851100-1

Sample Number	23121879-9
Sampled Date	Nov 23, 2023 3:00 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	2800000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Water Testing							
BOD *	mg/L	-	2	2154	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	194	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	6.3	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	100	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	7.2	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	428	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	101	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta B.

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851100-1

Sample Number	23121879-9
Sampled Date	Nov 23, 2023 3:00 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	2528	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารที่ละลายได้ทั้งหมดในน้ำใช้ = 81 มิลลิกรัมต่อลิตร

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851101-1

Sample Number	23121879-10
Sampled Date	Nov 23, 2023 2:43 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	1100000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Water Testing							
BOD *	mg/L	-	2	84.5	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	14	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	6.9	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	2.8	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	276	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	54.8	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta B.

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851101-1

Sample Number	23121879-10
Sampled Date	Nov 23, 2023 2:43 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	36	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารที่ละลายได้ทั้งหมดในน้ำใช้ = 81 มิลลิกรัมต่อลิตร

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851102-1

Sample Number	23121879-11
Sampled Date	Nov 23, 2023 2:30 PM
Sample Description	น้ำใช้
Location	น้ำใช้ภายในโรงแรม
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in one plastic bottle, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Water Testing						
Total Dissolved solids Dried at 180 degree C	mg/L	-	5	81	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Jan 04, 2024
Report Number : 2876565-1

Sample Number	23133971-5
Sampled Date	Dec 22, 2023 2:38 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	13000000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Water Testing							
BOD *	mg/L	-	2	442	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	103	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.5	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	22.0	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	3.2	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	296	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	111	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Jan 04, 2024
Report Number : 2876565-1

Sample Number	23133971-5
Sampled Date	Dec 22, 2023 2:38 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 1
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	840	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารที่ละลายได้ทั้งหมด = 96 mg/L

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Jan 04, 2024
Report Number : 2876566-1

Sample Number	23133971-6
Sampled Date	Dec 22, 2023 2:20 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	7000000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Water Testing							
BOD *	mg/L	-	2	97.5	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	4	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.7	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	0.2	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	1.0	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	236	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	73.6	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta B.

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Jan 04, 2024
Report Number : 2876566-1

Sample Number	23133971-6
Sampled Date	Dec 22, 2023 2:20 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 1
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	107	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารที่ละลายได้ทั้งหมด = 96 mg/L

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Jan 04, 2024
Report Number : 2876567-1

Sample Number	23133971-7
Sampled Date	Dec 22, 2023 2:48 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	11000000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Water Testing							
BOD *	mg/L	-	2	810	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	162	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	6.3	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	170	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	7.3	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	360	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	82.3	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Jan 04, 2024
Report Number : 2876567-1

Sample Number	23133971-7
Sampled Date	Dec 22, 2023 2:48 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	น้ำทิ้งก่อนเข้าระบบบ่อที่ 2
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	2196	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารที่ละลายได้ทั้งหมด = 96 mg/L

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Jan 04, 2024
Report Number : 2876568-1

Sample Number	23133971-8
Sampled Date	Dec 22, 2023 2:29 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Fecal Coliform	MPN/100mL	-	-	7900000.0	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Water Testing							
BOD *	mg/L	-	2	72.0	≤30	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5210 B	Songkhla
Oil & Grease	mg/L	-	3	3	≤20	In-house method : STM 13-006 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 5520 B	Songkhla
pH at 25 degree C		-	-	7.0	5.0-9.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Settleable Solid *	mL/L/hr	-	0.1	0.1	≤0.5	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 F	Songkhla
Sulfide *	mg/L	-	0.5	2.4	≤1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-S2 (C, F)	Songkhla
Total Dissolved Solids Dried at 103-105 degree C *	mg/L	-	5	224	(1)	In-house method : STM 04-010 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla
Total Kjeldahl Nitrogen as N *	mg/L	0.15	1.0	50.0	≤35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Norg (C)	Bangkok

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta B.

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Jan 04, 2024
Report Number : 2876568-1

Sample Number	23133971-8
Sampled Date	Dec 22, 2023 2:29 PM
Sample Description	น้ำระบบบำบัดน้ำเสีย
Location	บ่อพักน้ำทิ้งก่อนปล่อยออกสู่สาธารณะบ่อ 2
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in one amber glass bottle and five plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Water Testing							
Total Suspended Solids	mg/L	-	5	42	≤40	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 D	Songkhla

Guideline : Notification of Ministry of Natural Resources and Environment November,7 ,B.E. 2548 on Effluent Control Standard from Types and Sized of Buildings, Type B.
(1) : The values are in addition to the Total Dissolved Solids of the water used not more than 500 mg/L.
Note : สารที่ละลายได้ทั้งหมด = 96 mg/L

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0166

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Jan 04, 2024
Report Number : 2876569-1

Sample Number	23133971-9
Sampled Date	Dec 22, 2023 3:00 PM
Sample Description	น้ำใช้
Location	น้ำใช้ภายในโรงแรม ก๊อกน้ำใช้ข้างป๋อม รปภ.
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in one plastic bottle, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Water Testing						
Total Dissolved solids Dried at 180 degree C	mg/L	-	5	96	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2540 C	Songkhla

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

Approved by

Ananta Boonphet
Scientist (2)

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736399-1

Sample Number	2371803-1
Sampled Date	Jul 24, 2023 1:15 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ลึก) สระใหญ่
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method STM No. 01-054 in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B - FDA BAM online, 2016 (Chapter 12)	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Sithichok Thongnguen
Scientist (3)

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736400-1

Sample Number	2371803-2
Sampled Date	Jul 24, 2023 1:15 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ตื้น) สระใหญ่
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method STM No. 01-054 in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B - FDA BAM online, 2016 (Chapter 12)	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Sithichok Thongnguen
Scientist (3)

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736401-1

Sample Number	2371803-3
Sampled Date	Jul 24, 2023 1:20 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ลึก) สระเล็ก
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method STM No. 01-054 in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B - FDA BAM online, 2016 (Chapter 12)	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Sithichok Thongnguen
Scientist (3)

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2371803
Date Received : Jul 25, 2023
Date Reported : Aug 04, 2023
Report Number : 2736402-1

Sample Number	2371803-4
Sampled Date	Jul 24, 2023 1:20 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ตื้น) สระเล็ก
Date Analysis Commenced	Jul 25, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method STM No. 01-054 in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B - FDA BAM online, 2016 (Chapter 12)	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Sithichok Thongnguen
Scientist (3)

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769819-1

Sample Number	2391738-3
Sampled Date	Aug 28, 2023 2:20 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 สระใหญ่
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in three plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Water Testing						
Ammonium	mg/L	-	0.06	<0.06	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-NH3 F	Bangkok
Chloride as Cl	mg/L	0.06	0.2	2322	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4110 B	Bangkok
Cyanuric acid	mg/L	2	7	Not Detected	Colorimetric Method	Bangkok
Nitrate as N	mg/L	0.06	0.2	1.1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4110 B	Bangkok
pH at 25 degree C		-	-	7.0	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Residual Free Chlorine	mg/L	-	0.1	0.3	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Cl (F)	Songkhla
Total Chlorine	mg/L	-	0.1	0.4	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Cl (F)	Songkhla
Total Hardness as CaCO3	mg/L	-	1	38	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2340 C	Songkhla

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta B.
Ananta Boonphet
Scientist (2)

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769820-1

Sample Number	2391738-4
Sampled Date	Aug 28, 2023 2:30 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 สระเล็ก
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in three plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Water Testing						
Ammonium	mg/L	-	0.06	<0.06	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-NH3 F	Bangkok
Chloride as Cl	mg/L	0.06	0.2	1945	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4110 B	Bangkok
Cyanuric acid	mg/L	2	7	Not Detected	Colorimetric Method	Bangkok
Nitrate as N	mg/L	0.06	0.2	1.0	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4110 B	Bangkok
pH at 25 degree C		-	-	7.1	In-house method : STM 13-001 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Residual Free Chlorine	mg/L	-	0.1	<0.1	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Cl (F)	Songkhla
Total Chlorine	mg/L	-	0.1	0.1	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Cl (F)	Songkhla
Total Hardness as CaCO3	mg/L	-	1	28	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2340 C	Songkhla

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta B.
Ananta Boonphet
Scientist (2)

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769821-1

Sample Number	2391738-5
Sampled Date	Aug 28, 2023 2:20 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ลึก) สระใหญ่
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769822-1

Sample Number	2391738-6
Sampled Date	Aug 28, 2023 2:20 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ตื้น)
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769823-1

Sample Number	2391738-7
Sampled Date	Aug 28, 2023 2:30 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ลึก)
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769824-1

Sample Number	2391738-8
Sampled Date	Aug 28, 2023 2:30 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ตื้น)
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23112005
Date Received : Sep 29, 2023
Date Reported : Oct 09, 2023
Report Number : 2787688-1

Sample Number	23112005-1
Sampled Date	Sep 28, 2023 12:23 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ลึก) สระใหญ่
Date Analysis Commenced	Sep 29, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Sithichok Thongnguen
Scientist (3)

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23112005
Date Received : Sep 29, 2023
Date Reported : Oct 09, 2023
Report Number : 2787688-1

Sample Number	23112005-2
Sampled Date	Sep 28, 2023 12:16 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ตื้น) สระใหญ่
Date Analysis Commenced	Sep 29, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Sithichok T.
Sithichok Thongnguen
Scientist (3)

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23112005
Date Received : Sep 29, 2023
Date Reported : Oct 09, 2023
Report Number : 2787688-1

Sample Number	23112005-3
Sampled Date	Sep 28, 2023 12:05 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ลึก) สระเล็ก
Date Analysis Commenced	Sep 29, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

SithichokT.
Sithichok Thongnguen
Scientist (3)

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23112005
Date Received : Sep 29, 2023
Date Reported : Oct 09, 2023
Report Number : 2787688-1

Sample Number	23112005-4
Sampled Date	Sep 28, 2023 12:00 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ตื้น) สระเล็ก
Date Analysis Commenced	Sep 29, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

SithichokT.
Sithichok Thongnguen
Scientist (3)

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822518-1

Sample Number	23113448-1
Sampled Date	Oct 26, 2023 2:05 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ลึก) สระใหญ่
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822519-1

Sample Number	23113448-2
Sampled Date	Oct 26, 2023 2:03 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ตื้น)
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822520-1

Sample Number	23113448-3
Sampled Date	Oct 26, 2023 2:15 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ลึก)
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Analysis / Test Report

TESTING
No.0009

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23113448
Date Received : Oct 27, 2023
Date Reported : Nov 06, 2023
Report Number : 2822521-1

Sample Number	23113448-4
Sampled Date	Oct 26, 2023 2:11 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ตื้น)
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Bangkok
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Bangkok
Pseudomonas aeruginosa *	in 100 mL	-	-	Not Detected	In-house method based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 01-054 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851092-1

Sample Number	23121879-1
Sampled Date	Nov 23, 2023 2:00 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 สระใหญ่
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in three plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Water Testing						
Ammonium	mg/L	-	0.06	<0.06	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-NH3 F	Bangkok
Chloride as Cl	mg/L	0.06	0.2	2345	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4110 B	Bangkok
Cyanuric acid	mg/L	2	7	Not Detected	Colorimetric Method	Bangkok
Nitrate as N	mg/L	0.06	0.2	1.3	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4110 B	Bangkok
pH at 25 degree C		-	-	6.3	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Residual Free Chlorine	mg/L	-	0.1	0.9	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Cl (F)	Songkhla
Total Chlorine	mg/L	-	0.1	1.0	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Cl (F)	Songkhla
Total Hardness as CaCO3	mg/L	-	1	30	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2340 C	Songkhla

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by

Ananta Boonphet
Scientist (2)

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851093-1

Sample Number	23121879-2
Sampled Date	Nov 23, 2023 2:10 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 สระเล็ก
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in three plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Water Testing						
Ammonium	mg/L	-	0.06	<0.06	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-NH3 F	Bangkok
Chloride as Cl	mg/L	0.06	0.2	2929	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4110 B	Bangkok
Cyanuric acid	mg/L	2	7	Not Detected	Colorimetric Method	Bangkok
Nitrate as N	mg/L	0.06	0.2	1.2	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4110 B	Bangkok
pH at 25 degree C		-	-	7.3	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500 - H (B)	Songkhla
Residual Free Chlorine	mg/L	-	0.1	0.2	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Cl (F)	Songkhla
Total Chlorine	mg/L	-	0.1	0.3	Based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 4500-Cl (F)	Songkhla
Total Hardness as CaCO3	mg/L	-	1	35	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 2340 C	Songkhla

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Ananta Boonphet
Scientist (2)

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851094-1

Sample Number	23121879-3
Sampled Date	Nov 23, 2023 2:03 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ลึก) สระใหญ่
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Songkhla
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Pseudomonas aeruginosa	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 14-039 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Songkhla
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Songkhla

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by

Chompoonuch F.

Chompoonuch Funtha
Supervisor

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851095-1

Sample Number	23121879-4
Sampled Date	Nov 23, 2023 2:00 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ตื้น)
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Songkhla
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Pseudomonas aeruginosa	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 14-039 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Songkhla
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Songkhla

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by

Chompoonuch F.

Chompoonuch Funtha
Supervisor

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851096-1

Sample Number	23121879-5
Sampled Date	Nov 23, 2023 2:15 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ลึก)
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Songkhla
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Pseudomonas aeruginosa	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 14-039 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Songkhla
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Songkhla

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by

Chompoonuch F.

Chompoonuch Funtha
Supervisor

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O :
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23121879
Date Received : Nov 24, 2023
Date Reported : Dec 04, 2023
Report Number : 2851097-1

Sample Number	23121879-6
Sampled Date	Nov 23, 2023 2:10 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ตื้น)
Date Analysis Commenced	Nov 24, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Songkhla
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Pseudomonas aeruginosa	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 14-039 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Songkhla
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Songkhla

Sampling By : Yuttapong Rattana , Sakkarin Panpheng

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by

Chompoonuch F.

Chompoonuch Funtha
Supervisor

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Dec 30, 2023
Report Number : 2876561-1

Sample Number	23133971-1
Sampled Date	Dec 22, 2023 2:02 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ลึก) สระใหญ่
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Songkhla
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Pseudomonas aeruginosa	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 14-039 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Songkhla
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Songkhla

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by

Chompoonuch F.

Chompoonuch Funtha
Supervisor

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Dec 30, 2023
Report Number : 2876562-1

Sample Number	23133971-2
Sampled Date	Dec 22, 2023 2:00 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 1 (ตื้น)
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Songkhla
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Pseudomonas aeruginosa	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 14-039 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Songkhla
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Songkhla

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by

Chompoonuch F.

Chompoonuch Funtha
Supervisor

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Dec 30, 2023
Report Number : 2876563-1

Sample Number	23133971-3
Sampled Date	Dec 22, 2023 2:10 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ลึก)
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Songkhla
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Pseudomonas aeruginosa	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 14-039 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Songkhla
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Songkhla

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by

Chompoonuch F.

Chompoonuch Funtha
Supervisor

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23133971
Date Received : Dec 23, 2023
Date Reported : Dec 30, 2023
Report Number : 2876564-1

Sample Number	23133971-4
Sampled Date	Dec 22, 2023 2:08 PM
Sample Description	สระว่ายน้ำ
Location	สระที่ 2 (ตื้น)
Date Analysis Commenced	Dec 23, 2023
Condition of Sample	Contained in two plastic bottles, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Escherichia coli	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, F	Songkhla
Fecal Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B, E	Songkhla
Pseudomonas aeruginosa	in 100 mL	-	-	Not Detected	In-house method in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 E	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	In-house method : STM No. 14-039 based on Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B and FDA Bacteriological Analytical Manual online, Chapter 12, 2016	Songkhla
Total Coliform	in 100 mL	-	-	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Songkhla

Sampling By : Thaksin Aintrom

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Approved by

Chompoonuch F.

Chompoonuch Funtha
Supervisor

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Accreditation No. 1031/47

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769817-1

Sample Number	2391738-1
Sampled Date	Aug 28, 2023 3:40 PM
Sample Description	ถังสารองน้ำใช้
Location	ถังที่ 1
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one plastic bottle, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Clostridium perfringens	in 100 mL	-	-	Not Detected	Not Detected	In-house method STM No. 01-012 in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9260 A,B - FDA BAM online, 2001 (Chapter 16)	Bangkok
Escherichia coli	in 100 mL	-	-	Not Detected	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 F	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	Not Detected	In-house method STM No. 01-054 in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B - FDA BAM online, 2016 (Chapter 12)	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Guideline : Thai Industrial Standard No. 257-2549 refer to Notification of the Ministry of Industry No. 3470 (B.E. 2549).

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Accreditation No. 1031/47

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location:

Lot ID: 2391738
Date Received : Aug 29, 2023
Date Reported : Sep 07, 2023
Report Number : 2769818-1

Sample Number	2391738-2
Sampled Date	Aug 28, 2023 3:45 PM
Sample Description	ถังสารองน้ำใช้
Location	ถังที่ 2
Date Analysis Commenced	Aug 29, 2023
Condition of Sample	Contained in one plastic bottle, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Guideline / Specification	Method	Testing Location
Microbiological Testing							
Clostridium perfringens	in 100 mL	-	-	Not Detected	Not Detected	In-house method STM No. 01-012 in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9260 A,B - FDA BAM online, 2001 (Chapter 16)	Bangkok
Escherichia coli	in 100 mL	-	-	Not Detected	Not Detected	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 F	Bangkok
Staphylococcus aureus	in 100 mL	-	-	Not Detected	Not Detected	In-house method STM No. 01-054 in connection with: - Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9213 B - FDA BAM online, 2016 (Chapter 12)	Bangkok
Total Coliform	in 100 mL	-	-	Not Detected	No Standard	Standard Methods for the Examination of Water and Wastewater. APHA, AWWA & WEF, 23rd ed., 2017, part 9221 B	Bangkok

Guideline : Thai Industrial Standard No. 257-2549 refer to Notification of the Ministry of Industry No. 3470 (B.E. 2549).

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)
- Analyte(s) marked * is/are not included in scope of Accreditation ISO/IEC 17025.
- The laboratory has been accepted as an accredited laboratory complying with the ISO/IEC 17025.

The above results are valid only for the analyzed/tested sample(s) as indicated in this report. No part of this report or certificate may be reproduced in any form without written consent from the Laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Suwannee Chuamkeaw
Section Head

Analysis / Test Report

Client : Stone Bitter Co., Ltd.
111 Soi Chengtalay 16, Srisoonthorn Road, Chengtalay, Thalang, Phuket Thailand 83110
P/O : สัญญาจ้าง
Project Name : Hilton Garden Inn Phuket Bangtao
Project Location :

Lot ID: 23113451
Date Received : Oct 27, 2023
Date Reported : Nov 13, 2023
Report Number : 2790057-1

Sample Number	23113451-1
Sampled Date	Oct 26, 2023 3:00 PM
Sample Description	เครื่องปรับอากาศ
Location	เครื่องปรับอากาศส่วนกลาง
Date Analysis Commenced	Oct 27, 2023
Condition of Sample	Swab placed in a vial of sterile buffered rinse solution, refrigerated, sample containers comply to pretreatment - preservation standards (APHA, USEPA)

Analyte	Unit	LOD	LOQ (LOR)	Result	Method	Testing Location
Microbiological Testing						
Legionella spp.	per Unit	-	-	Not Detected	ISO 11731 (2017)	Bangkok

Sampling By : Yuttapong Rattana

Remark :
- LOD : Limit of Detection
- "<" : Lower than LOQ (Limit of Quantitation) / LOR (Limit of Reporting)

Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. No part of this report may be reproduced in any form without written consent from the laboratory. ALS Laboratory Group (Thailand) strongly recommends that this report is not reproduced except in full.

Approved by

Sithichok Thongnguen
Scientist (3)

ภาคผนวก ง

กฎหมายที่เกี่ยวข้อง

ประกาศกระทรวงทรัพยากรธรรมชาติและสิ่งแวดล้อม

เรื่อง กำหนดมาตรฐานควบคุมการระบายน้ำทิ้ง จากอาคารบางประเภทและบางขนาด

โดยที่ได้มีการปฏิรูประบบราชการโดยให้มีการจัดตั้งกระทรวงทรัพยากรธรรมชาติและสิ่งแวดล้อมขึ้นมา และให้โอนภารกิจของกระทรวงวิทยาศาสตร์ เทคโนโลยีและสิ่งแวดล้อม ในส่วนที่เกี่ยวข้องกับพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ ไปเป็นของกระทรวงทรัพยากรธรรมชาติและสิ่งแวดล้อม ประกอบกับเป็นการสมควรให้คณะกรรมการควบคุมมลพิษเป็นผู้พิจารณาเห็นชอบกับวิธีการตรวจหาค่ามาตรฐานการระบายน้ำทิ้ง นอกเหนือจากวิธีการที่กำหนดไว้แทนกรมควบคุมมลพิษ จึงสมควรแก้ไขปรับปรุงประกาศกระทรวงวิทยาศาสตร์ เทคโนโลยีและสิ่งแวดล้อม เรื่อง กำหนดมาตรฐานควบคุมการระบายน้ำทิ้งจากอาคารบางประเภทและบางขนาด

อาศัยอำนาจตามความในมาตรา ๕๕ แห่งพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ แก้ไขโดยมาตรา ๑๑๔ แห่งพระราชกฤษฎีกาแก้ไขบทบัญญัติให้สอดคล้องกับการโอนอำนาจหน้าที่ของส่วนราชการ ให้เป็นไปตามพระราชบัญญัติปรับปรุงกระทรวง ทบวง กรม พ.ศ. ๒๕๔๕ พ.ศ. ๒๕๔๕ อันเป็นพระราชบัญญัติที่มีบทบัญญัติบางประการเกี่ยวกับการจำกัดสิทธิและเสรีภาพของบุคคล ซึ่งมาตรา ๒๙ ประกอบกับมาตรา ๓๕ มาตรา ๔๘ มาตรา ๕๐ และมาตรา ๕๑ ของรัฐธรรมนูญแห่งราชอาณาจักรไทยบัญญัติให้กระทำได้ โดยอาศัยอำนาจตามบทบัญญัติแห่งกฎหมายรัฐมนตรีว่าการกระทรวงทรัพยากรธรรมชาติและสิ่งแวดล้อม โดยคำแนะนำของคณะกรรมการควบคุมมลพิษและโดยความเห็นชอบของคณะกรรมการสิ่งแวดล้อมแห่งชาติ จึงออกประกาศไว้ ดังต่อไปนี้

ข้อ ๑ ให้ยกเลิกประกาศกระทรวงวิทยาศาสตร์ เทคโนโลยีและสิ่งแวดล้อม เรื่อง กำหนดมาตรฐานควบคุมการระบายน้ำทิ้งจากอาคารบางประเภทและบางขนาด ลงวันที่ ๑๐ มกราคม พ.ศ. ๒๕๓๗

ข้อ ๒ ในประกาศนี้

“อาคาร” หมายความว่า อาคารที่ก่อสร้างขึ้น ไม่ว่าจะมีลักษณะเป็นอาคารหลังเดียว หรือเป็นกลุ่มของอาคารซึ่งตั้งอยู่ภายในพื้นที่ซึ่งเป็นบริเวณเดียวกัน และไม่ว่าจะมีท่อระบายน้ำท่อเดียว หรือมีหลายท่อที่เชื่อมติดต่อกันระหว่างอาคารหรือไม่ก็ตาม ซึ่งได้แก่

(๑) อาคารชุด ตามกฎหมายว่าด้วยอาคารชุด

(๒) โรงแรม ตามกฎหมายว่าด้วยโรงแรม

(๓) หอพัก ตามกฎหมายว่าด้วยหอพัก

(๔) สถานบริการประเภทสถานอาบน้ำ นวดหรืออบตัว ซึ่งมีผู้ให้บริการแก่ลูกค้า ตามกฎหมายว่าด้วยสถานบริการ

(๕) โรงพยาบาลของทางราชการหรือสถานพยาบาล ตามกฎหมายว่าด้วยสถานพยาบาล

(๖) อาคารโรงเรียนเอกชน ตามกฎหมายว่าด้วยโรงเรียนเอกชน โรงเรียนของทางราชการ อาคารสถาบันอุดมศึกษาของเอกชน ตามกฎหมายว่าด้วยสถาบันอุดมศึกษาของเอกชนและสถาบันอุดมศึกษาของทางราชการ

(๗) อาคารที่ทำการของทางราชการ รัฐวิสาหกิจ หรือองค์การระหว่างประเทศและของเอกชน

(๘) อาคารของศูนย์การค้าหรือห้างสรรพสินค้า

(๙) ตลาด ตามกฎหมายว่าด้วยการสาธารณสุข แต่ไม่รวมถึง ท่าเทียบเรือประมง สะพานปลา หรือกิจการแพปลา

(๑๐) ภัตตาคารหรือร้านอาหาร

“น้ำทิ้ง” หมายความว่า น้ำเสียที่ผ่านระบบบำบัดน้ำเสียแล้วจนเป็นไปตามมาตรฐานควบคุมการระบายน้ำทิ้งตามที่กำหนดไว้ในประกาศนี้

ข้อ ๓ ให้แบ่งประเภทของอาคารตามข้อ ๒ ออกเป็น ๕ ประเภท คือ

(๑) อาคารประเภท ก.

(๒) อาคารประเภท ข.

(๓) อาคารประเภท ค.

(๔) อาคารประเภท ง.

(๕) อาคารประเภท จ.

ข้อ ๔ อาคารประเภท ก. หมายความถึง อาคารดังต่อไปนี้

(๑) อาคารชุดที่มีจำนวนห้องสำหรับใช้เป็นที่อยู่อาศัยรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคารตั้งแต่ ๕๐๐ ห้องนอนขึ้นไป

(๒) โรงแรมที่มีจำนวนห้องสำหรับใช้เป็นห้องพักรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคารตั้งแต่ ๒๐๐ ห้องขึ้นไป

(๓) โรงพยาบาลของทางราชการ รัฐวิสาหกิจหรือสถานพยาบาล ตามกฎหมายว่าด้วยสถานพยาบาลที่มีเตียงสำหรับผู้ป่วยไว้ค้างคืนรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๓๐ เตียงขึ้นไป

(๔) อาคารโรงเรียนเอกชน โรงเรียนของทางราชการ สถาบันอุดมศึกษาของเอกชน หรือสถาบันอุดมศึกษาของทางราชการที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๒๕,๐๐๐ ตารางเมตรขึ้นไป

(๕) อาคารที่ทำการของทางราชการ รัฐวิสาหกิจ องค์การระหว่างประเทศ หรือของเอกชนที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๕๕,๐๐๐ ตารางเมตรขึ้นไป

(๖) อาคารของศูนย์การค้าหรือห้างสรรพสินค้าที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๒๕,๐๐๐ ตารางเมตรขึ้นไป

(๗) ตลาดที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๒,๕๐๐ ตารางเมตรขึ้นไป

(๘) ภัตตาคารหรือร้านอาหารที่มีพื้นที่ให้บริการรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๒,๕๐๐ ตารางเมตรขึ้นไป

ข้อ ๕ อาคารประเภท ข. หมายความถึง อาคารดังต่อไปนี้

(๑) อาคารชุดที่มีจำนวนห้องสำหรับใช้เป็นที่อยู่อาศัยรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคารตั้งแต่ ๑๐๐ ห้องนอน แต่ไม่ถึง ๕๐๐ ห้องนอน

(๒) โรงแรมที่มีจำนวนห้องสำหรับใช้เป็นห้องพักรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคารตั้งแต่ ๖๐ ห้อง แต่ไม่ถึง ๒๐๐ ห้อง

(๓) หอพักที่มีจำนวนห้องสำหรับใช้เป็นที่อยู่อาศัยรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคารตั้งแต่ ๒๕๐ ห้องขึ้นไป

(๔) สถานบริการที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคารตั้งแต่ ๕,๐๐๐ ตารางเมตรขึ้นไป

(๕) โรงพยาบาลของทางราชการ รัฐวิสาหกิจ หรือสถานพยาบาล ตามกฎหมายว่าด้วยสถานพยาบาลที่มีเตียงสำหรับผู้ป่วยไว้ค้างคืนรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๑๐ เตียง แต่ไม่ถึง ๓๐ เตียง

(๖) อาคารโรงเรียนเอกชน โรงเรียนของทางราชการ สถาบันอุดมศึกษาของเอกชน หรือสถาบันอุดมศึกษาของทางราชการที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๕,๐๐๐ ตารางเมตร แต่ไม่ถึง ๒๕,๐๐๐ ตารางเมตร

(๗) อาคารที่ทำการของทางราชการ รัฐวิสาหกิจ องค์การระหว่างประเทศ หรือของเอกชน ที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๑๐,๐๐๐ ตารางเมตร แต่ไม่ถึง ๕๕,๐๐๐ ตารางเมตร

(๘) อาคารของศูนย์การค้าหรือห้างสรรพสินค้าที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๕,๐๐๐ ตารางเมตร แต่ไม่ถึง ๒๕,๐๐๐ ตารางเมตร

(๙) ตลาดที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๑,๕๐๐ ตารางเมตร แต่ไม่ถึง ๒,๕๐๐ ตารางเมตร

(๑๐) ภัตตาคารหรือร้านอาหารที่มีพื้นที่ให้บริการรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคาร ตั้งแต่ ๕๐๐ ตารางเมตร แต่ไม่ถึง ๒,๕๐๐ ตารางเมตร

ข้อ ๖ อาคารประเภท ค. หมายความถึง อาคารดังต่อไปนี้

(๑) อาคารชุดที่มีจำนวนห้องสำหรับใช้เป็นที่อยู่อาศัยรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคาร ไม่ถึง ๑๐๐ ห้องนอน

(๒) โรงแรมที่มีจำนวนห้องสำหรับใช้เป็นห้องพักรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคาร ไม่ถึง ๖๐ ห้อง

(๓) หอพักที่มีจำนวนห้องสำหรับใช้เป็นที่อยู่อาศัยรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคาร ตั้งแต่ ๕๐ ห้อง แต่ไม่ถึง ๒๕๐ ห้อง

(๔) สถานบริการที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคารตั้งแต่ ๑,๐๐๐ ตารางเมตร แต่ไม่ถึง ๕,๐๐๐ ตารางเมตร

(๕) อาคารที่ทำการของทางราชการ รัฐวิสาหกิจ องค์การระหว่างประเทศ หรือของเอกชน ที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๕,๐๐๐ ตารางเมตร แต่ไม่ถึง ๑๐,๐๐๐ ตารางเมตร

(๖) ตลาดที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคารหรือกลุ่มของอาคารตั้งแต่ ๑,๐๐๐ ตารางเมตร แต่ไม่ถึง ๑,๕๐๐ ตารางเมตร

(๗) ภัตตาคารหรือร้านอาหารที่มีพื้นที่ให้บริการรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคาร ตั้งแต่ ๒๕๐ ตารางเมตร แต่ไม่ถึง ๕๐๐ ตารางเมตร

ข้อ ๗ อาคารประเภท ง. หมายความถึง อาคารดังต่อไปนี้

(๑) หอพักที่มีจำนวนห้องสำหรับใช้เป็นที่อยู่อาศัยรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคาร ตั้งแต่ ๑๐ ห้อง แต่ไม่ถึง ๕๐ ห้อง

(๒) ตลาดที่มีพื้นที่ใช้สอยรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคารตั้งแต่ ๕๐๐ ตารางเมตร แต่ไม่ถึง ๑,๐๐๐ ตารางเมตร

(๓) ภัตตาคารหรือร้านอาหารที่มีพื้นที่ให้บริการรวมกันทุกชั้นของอาคาร หรือกลุ่มของอาคาร ตั้งแต่ ๑๐๐ ตารางเมตร แต่ไม่ถึง ๒๕๐ ตารางเมตร

ข้อ ๘ อาคารประเภท จ. หมายความถึง ภัตตาคารหรือร้านอาหารที่มีพื้นที่ให้บริการรวมกันทุกชั้นไม่ถึง ๑๐๐ ตารางเมตร

ข้อ ๙ มาตรฐานควบคุมการระบายน้ำทิ้งจากอาคาร ประเภท ก. ต้องมีค่าดังต่อไปนี้

(๑) ความเป็นกรดและด่าง (PH) ต้องมีค่าระหว่าง ๕-๙

(๒) บีโอดี (BOD) ต้องมีค่าไม่เกิน ๒๐ มิลลิกรัมต่อลิตร

(๓) สารแขวนลอย (Suspended Solids) ต้องมีค่าไม่เกิน ๓๐ มิลลิกรัมต่อลิตร

(๔) ซัลไฟด์ (Sulfide) ต้องมีค่าไม่เกิน ๑.๐ มิลลิกรัมต่อลิตร

(๕) สารที่ละลายได้ทั้งหมด (Total Dissolved Solids) ต้องมีค่าเพิ่มขึ้นจากปริมาณสารละลายในน้ำใช้ตามปกติไม่เกิน ๕๐๐ มิลลิกรัมต่อลิตร

(๖) ตะกอนหนัก (Settleable Solids) ต้องมีค่าไม่เกิน ๐.๕ มิลลิลิตรต่อลิตร

(๗) น้ำมันและไขมัน (Fat Oil and Grease) ต้องมีค่าไม่เกิน ๒๐ มิลลิกรัมต่อลิตร

(๘) ทีเคเอ็น (TKN) ต้องมีค่าไม่เกิน ๓๕ มิลลิกรัมต่อลิตร

ข้อ ๑๐ มาตรฐานควบคุมการระบายน้ำทิ้งจากอาคาร ประเภท ข. ต้องเป็นไปตามข้อ ๙ เว้นแต่

(๑) บีโอดี ต้องมีค่าไม่เกิน ๓๐ มิลลิกรัมต่อลิตร

(๒) สารแขวนลอย ต้องมีค่าไม่เกิน ๔๐ มิลลิกรัมต่อลิตร

ข้อ ๑๑ มาตรฐานควบคุมการระบายน้ำทิ้งจากอาคาร ประเภท ค. ต้องเป็นไปตามข้อ ๙ เว้นแต่

(๑) บีโอดี ต้องมีค่าไม่เกิน ๔๐ มิลลิกรัมต่อลิตร

(๒) สารแขวนลอย ต้องมีค่าไม่เกิน ๕๐ มิลลิกรัมต่อลิตร

(๓) ซัลไฟด์ ต้องมีค่าไม่เกิน ๓.๐ มิลลิกรัมต่อลิตร

(๔) ค่าทีเคเอ็น ต้องมีค่าไม่เกิน ๔๐ มิลลิกรัมต่อลิตร

ข้อ ๑๒ มาตรฐานควบคุมการระบายน้ำทิ้งจากอาคาร ประเภท ง. ต้องเป็นไปตามข้อ ๙ เว้นแต่

(๑) บีโอดี ต้องมีค่าไม่เกิน ๕๐ มิลลิกรัมต่อลิตร

(๒) สารแขวนลอย ต้องมีค่าไม่เกิน ๕๐ มิลลิกรัมต่อลิตร

(๓) ซัลไฟด์ ต้องมีค่าไม่เกิน ๔.๐ มิลลิกรัมต่อลิตร

(๔) ค่าทีเคเอ็น ต้องมีค่าไม่เกิน ๔๐ มิลลิกรัมต่อลิตร

ข้อ ๑๓ มาตรฐานควบคุมการระบายน้ำทิ้งจากอาคาร ประเภท จ. ต้องมีค่าดังต่อไปนี้

(๑) ความเป็นกรดและด่างต้องมีค่าระหว่าง ๕-๙

(๒) บีโอดี ต้องมีค่าไม่เกิน ๒๐๐ มิลลิกรัมต่อลิตร

(๓) สารแขวนลอย ต้องมีค่าไม่เกิน ๖๐ มิลลิกรัมต่อลิตร

(๔) น้ำมันและไขมัน ต้องมีค่าไม่เกิน ๑๐๐ มิลลิกรัมต่อลิตร

ข้อ ๑๔ การตรวจสอบมาตรฐานการระบายน้ำทิ้งจากอาคาร ให้ใช้วิธีการดังต่อไปนี้

(๑) การตรวจสอบค่าความเป็นกรดและด่างให้กระทำโดยใช้เครื่องวัดความเป็นกรดและด่างของน้ำ (PH Meter)

(๒) การตรวจสอบค่าบีโอดีให้กระทำโดยใช้วิธีการอะไซด์โมดิฟิเคชั่น (Azide Modification) ที่อุณหภูมิ ๒๐ องศาเซลเซียส เป็นเวลา ๕ วัน ติดต่อกันหรือวิธีการอื่นที่คณะกรรมการควบคุมมลพิษให้ความเห็นชอบ

(๓) การตรวจสอบค่าสารแขวนลอยให้กระทำโดยใช้วิธีการกรองผ่านกระดาษกรองใยแก้ว (Glass Fibre Filter Disc)

(๔) การตรวจสอบค่าซัลไฟด์ให้กระทำโดยใช้วิธีการไตเตรท (Titrate)

(๕) การตรวจสอบค่าสารที่ละลายได้ทั้งหมดให้กระทำโดยใช้วิธีการระเหยแห้งระหว่างอุณหภูมิ ๑๐๓ องศาเซลเซียส ถึงอุณหภูมิ ๑๐๕ องศาเซลเซียส ในเวลา ๑ ชั่วโมง

(๖) การตรวจสอบค่าตะกอนหนักให้กระทำโดยใช้วิธีการกรวยอิมฮอฟฟ์ (Imhoff cone) ขนาดบรรจุ ๑,๐๐๐ ลูกบาศก์เซนติเมตร ในเวลา ๑ ชั่วโมง

(๗) การตรวจสอบค่าน้ำมันและไขมันให้กระทำโดยใช้วิธีการสกัดด้วยตัวทำละลาย แล้วแยกหาน้ำหนักของน้ำมันและไขมัน

(๘) การตรวจสอบค่าทีเคเอ็นให้กระทำโดยใช้วิธีการเจลดาห์ล (Kjeldahl)

ข้อ ๑๕ การคิดคำนวณพื้นที่ใช้สอย จำนวนอาคารและจำนวนห้องของอาคาร หรือกลุ่มของอาคาร ให้เป็นไปตามวิธีการที่คณะกรรมการควบคุมมลพิษกำหนด โดยประกาศในราชกิจจานุเบกษา

ข้อ ๑๖ วิธีการเก็บตัวอย่างน้ำ ความถี่ และระยะเวลาในการเก็บตัวอย่างน้ำ ให้เป็นไปตามที่คณะกรรมการควบคุมมลพิษกำหนด โดยประกาศในราชกิจจานุเบกษา

ข้อ ๑๗ ประกาศนี้ให้ใช้บังคับตั้งแต่วันถัดจากวันประกาศในราชกิจจานุเบกษาเป็นต้นไป

ประกาศ ณ วันที่ ๗ พฤศจิกายน พ.ศ. ๒๕๔๘

ยงยุทธ ติยะไพรัช

รัฐมนตรีว่าการกระทรวงทรัพยากรธรรมชาติและสิ่งแวดล้อม

ประกาศกระทรวงอุตสาหกรรม

ฉบับที่ ๓๔๗๐ (พ.ศ. ๒๕๔๙)

ออกตามความในพระราชบัญญัติมาตรฐานผลิตภัณฑ์อุตสาหกรรม

พ.ศ. ๒๕๑๑

เรื่อง ยกเลิกมาตรฐานผลิตภัณฑ์อุตสาหกรรม

น้ำบริโภค เล่ม 1 ข้อกำหนดเกณฑ์คุณภาพ

และกำหนดมาตรฐานผลิตภัณฑ์อุตสาหกรรม

น้ำบริโภค

โดยที่เป็นการสมควรปรับปรุงมาตรฐานผลิตภัณฑ์อุตสาหกรรม น้ำบริโภค เล่ม 1 ข้อกำหนดเกณฑ์คุณภาพ มาตรฐานเลขที่ มอก. 257 เล่ม 1-2521

อาศัยอำนาจตามความในมาตรา ๑๕ แห่งพระราชบัญญัติมาตรฐานผลิตภัณฑ์อุตสาหกรรม พ.ศ. ๒๕๑๑ รัฐมนตรีว่าการกระทรวงอุตสาหกรรมออกประกาศยกเลิกประกาศกระทรวงอุตสาหกรรม ฉบับที่ ๓๓๒ (พ.ศ. ๒๕๒๑) เรื่อง กำหนดมาตรฐานผลิตภัณฑ์อุตสาหกรรม น้ำบริโภค เล่ม 1 ข้อกำหนดเกณฑ์คุณภาพ ลงวันที่ ๘ พฤษภาคม พ.ศ. ๒๕๒๑ และออกประกาศกำหนดมาตรฐานผลิตภัณฑ์อุตสาหกรรม น้ำบริโภค มาตรฐานเลขที่ มอก. 257-2549 ขึ้นใหม่ ดังมีรายการละเอียดต่อท้ายประกาศนี้

ทั้งนี้ ให้มีผลเมื่อพ้นกำหนด ๑๘๐ วัน นับแต่วันที่ประกาศในราชกิจจานุเบกษาเป็นต้นไป

ประกาศ ณ วันที่ ๒๔ มีนาคม พ.ศ. ๒๕๔๙

สุริยะ จึงรุ่งเรืองกิจ

รัฐมนตรีว่าการกระทรวงอุตสาหกรรม

มาตรฐานผลิตภัณฑ์อุตสาหกรรม
น้ำบริโภค

1. ขอบข่าย

1.1 มาตรฐานผลิตภัณฑ์อุตสาหกรรมนี้ครอบคลุมน้ำที่ใช้บริโภคทั่วไปและน้ำที่ใช้ในอุตสาหกรรมอาหาร

2. บทนิยาม

ความหมายของคำที่ใช้ในมาตรฐานผลิตภัณฑ์อุตสาหกรรมนี้ มีดังต่อไปนี้

2.1 น้ำบริโภค หมายถึง น้ำที่ใช้ดื่ม รวมทั้งน้ำที่ใช้ทำอาหารและเครื่องดื่ม

2.2 หน่วยแพลทินัม-โคบอลต์ (platinum-cobalt scale) หมายถึง หน่วยวัดระดับความเข้มของสีแท้ (true colour) ของน้ำ โดยเปรียบเทียบกับสีของสารละลายมาตรฐานโพแทสเซียมคลอโรแพลทิเนตกับโคบอลต์ (II) คลอไรด์

2.3 หน่วยเอ็นทียู (nephelometric turbidity unit, NTU) หมายถึง หน่วยวัดความขุ่นในน้ำโดยวิธีเนฟีโลเมตรี

3. ประเภท

3.1 น้ำบริโภค แบ่งเป็น 2 ประเภท คือ

3.1.1 ประเภทที่ 1 บรรจุในภาชนะบรรจุปิดสนิท

3.1.2 ประเภทที่ 2 ไม่บรรจุในภาชนะบรรจุ

4. คุณลักษณะที่ต้องการ

4.1 ลักษณะทั่วไป

ต้องปราศจากสิ่งแปลมปลอมและกลิ่นและรสที่ไม่พึงประสงค์หรือเป็นที่น่ารังเกียจ

การทดสอบให้ทำโดยการตรวจพินิจ

4.2 คุณลักษณะทางฟิสิกส์

4.2.1 สี

ต้องไม่เกิน 5 หน่วยแพลทินัม-โคบอลต์

การทดสอบให้ปฏิบัติตาม Standard Methods FOR THE Examination of Water and Wastewater 20th Edition 1998 ข้อ 2120 B

4.2.2 ความขุ่น

ต้องไม่เกิน 5 หน่วยเอ็นทียู

การทดสอบให้ปฏิบัติตาม Standard Methods for the Examination of Water and Wastewater 20th Edition 1998 ข้อ 2130 B

4.2.3 ค่าความเป็นกรด-ด่าง

ต้องอยู่ระหว่าง 6.5 ถึง 8.5

การทดสอบให้ปฏิบัติตาม Standard Methods FOR THE Examination of Water and Wastewater 20th Edition 1998 ข้อ 4500-H^+B

4.3 คุณลักษณะทางเคมี

4.3.1 ประเภทที่ 1 ให้เป็นไปตามตารางที่ 1ก.

4.3.2 ประเภทที่ 2 ให้เป็นไปตามตารางที่ 1ก. อาจอนุโลมให้เป็นไปตามตารางที่ 1ข. ได้ชั่วคราว

4.4 สารที่เป็นพิษ

ให้เป็นไปตามตารางที่ 2

ตารางที่ 1ก. คุณลักษณะทางเคมี

(ข้อ 4.3.1 และข้อ 4.3.2)

ลำดับที่	รายการ	เกณฑ์ที่กำหนดสูงสุด มิลลิกรัมต่อลูกบาศก์เดซิเมตร	วิธีวิเคราะห์*
1	ปริมาณสารที่ละลายทั้งหมด (total dissolved solids)	500	ข้อ 2540 C
2	เหล็ก	0.3	ข้อ 3111B หรือข้อ 3111C
3	แมงกานีส	0.05	ข้อ 3111B
4	ทองแดง	1.0	ข้อ 3111 B
5	สังกะสี	3	ข้อ 3111 B
6	ความกระด้างทั้งหมด (คำนวณเป็นแคลเซียมคาร์บอเนต)	100	ข้อ 2340C
7	ซัลเฟต	200	ข้อ 4500-SO_4^{2-}E
8	คลอไรด์	250	ข้อ 4500-Cl^-B
9	ฟลูออไรด์	0.7	ข้อ 4500-F^-C
10	ไนเทรต (คำนวณเป็น ไนโตรเจน)	4	ข้อ 4500-NO_3^-D
11	ลิเนียร์อัลคิลเบนซีนซัลโฟเนต	0.2	ข้อ 5540 C
12	ฟีนอลิกซับสแตนซ์	0.001	ข้อ 5530 C

หมายเหตุ ** หมายถึง Standard Methods FOR THE Examination of Water and Wastewater 20th Edition 1998*

ตารางที่ 1ข. คุณลักษณะทางเคมีอนุโลมของน้ำบริโภคประเภทที่ 2

(ข้อ 4.3.2)

ลำดับที่	รายการ	เกณฑ์ที่กำหนดสูงสุด มิลลิกรัมต่อลูกบาศก์เดซิเมตร	วิธีวิเคราะห์*
1	ปริมาณสารที่ละลายทั้งหมด	600	ข้อ 2540 C
2	แมงกานีส	0.1	ข้อ 3111 B
3	ความกระด้างทั้งหมด (คำนวณเป็นแคลเซียมคาร์บอเนต)	300	ข้อ 2340 C
4	ซัลเฟต	250	ข้อ 4500–SO_4^{2-} E
5	ฟลูออไรด์	1	ข้อ 4500–F^- C
6	ไนเทรต (คำนวณเป็น ไนโตรเจน)	10	ข้อ 4500–NO_3^- D
7	ฟีนอลิกซับสแตนซ์	0.005	ข้อ 5530 C

หมายเหตุ ** หมายถึง Standard Methods FOR THE Examination of Water and Wastewater 20th Edition 1998*

5. สุขลักษณะ

5.1 สุขลักษณะในการทำน้ำบริโภค ให้เป็นไปตาม มอก.34

5.2 จุลินทรีย์ที่มีในน้ำบริโภค ต้องไม่เกินเกณฑ์ที่กำหนดดังนี้

5.2.1 โคลิฟอร์มแบคทีเรีย ต้องน้อยกว่า 1.1 ในตัวอย่าง 100 ลูกบาศก์เซนติเมตร โดยวิธีมัลติเพิลทิวบ์เฟอร์เมนเทชันเทคนิค (multiple tube fermentation technique)

5.2.2 *เอสเชอริเชีย โคไล (Escherichia coli)* ต้องไม่พบในตัวอย่าง 100 ลูกบาศก์เซนติเมตร

5.2.3 *สตาฟิโลค็อกคัส ออเรียส (Staphylococcus aureus)* ต้องไม่พบในตัวอย่าง 100 ลูกบาศก์เซนติเมตร

5.2.4 *ซาลโมเนลลา (Salmonella)* ต้องไม่พบในตัวอย่าง 100 ลูกบาศก์เซนติเมตร

5.2.5 *คลอสตริเดียม เพอร์ฟริงเจนส์ (Clostridium perfringens)* ต้องไม่พบในตัวอย่าง 100 ลูกบาศก์เซนติเมตร

5.2.6 ในกรณีที่มีโรคระบาดทางน้ำในท้องถิ่นนั้น ให้ตรวจจุลินทรีย์ที่เป็นสาเหตุของโรคระบาดในขณะนั้นด้วย เช่น อหิวาตกโรค ไทฟอยด์ บิด

การทดสอบให้ปฏิบัติตามข้อ 9.3

ตารางที่ 2 สารที่เป็นพิษ

(ข้อ 4.4)

ลำดับที่	รายการ	เกณฑ์ที่กำหนดสูงสุด มิลลิกรัมต่อลูกบาศก์เดซิเมตร	วิธีวิเคราะห์*
1	ปรอท	0.001	ข้อ 3112B
2	ตะกั่ว	0.01	ข้อ 3113B
3	สารหนู	0.01	ข้อ 3113B
4	ซีลีเนียม	0.01	ข้อ 3113B
5	โครเมียม	0.05	ข้อ 3113B
6	ไซยาไนด์	0.07	ข้อ 4500-CN^-F
7	แคดเมียม	0.003	ข้อ 3113B
8	แบเรียม	0.7	ข้อ 3113B

หมายเหตุ ** หมายถึง Standard Methods FOR THE Examination of Water and Wastewater 20th Edition 1998*

6. การบรรจุ

6.1 ให้บรรจุน้ำบริโภคในภาชนะบรรจุที่สะอาด มีฝาหรือจุกปิด ผนึกโดยรอบระหว่างฝาหรือจุกกับภาชนะบรรจุ และเมื่อเปิดใช้แล้วสิ่งที่ปิดผนึกหรือส่วนที่ปิดผนึกนั้นเสียไป

6.2 ปริมาตรสุทธิของน้ำบริโภคในแต่ละภาชนะบรรจุ ต้องไม่น้อยกว่าที่ระบุไว้ที่ฉลาก

7. เครื่องหมายและฉลาก

7.1 ที่ภาชนะบรรจุน้ำบริโภคทุกหน่วย อย่างน้อยต้องมีเลข อักษร หรือเครื่องหมายแจ้งรายละเอียดต่อไปนี้ให้เห็นได้ง่าย ชัดเจน

(1) ชื่อผลิตภัณฑ์ตามมาตรฐานนี้หรือชื่ออื่นที่สื่อความหมายว่าเป็นผลิตภัณฑ์ตามมาตรฐานนี้

(2) วัน เดือน ปีที่บรรจุ

(3) ปริมาตรสุทธิ เป็นลูกบาศก์เซนติเมตร (มิลลิลิตร) หรือลูกบาศก์เดซิเมตร (ลิตร)

(4) รหัสรุ่นที่ทำ

(5) ชื่อผู้ทำหรือโรงงานที่ทำ พร้อมสถานที่ตั้ง หรือเครื่องหมายการค้าที่จดทะเบียน

ในกรณีที่ใช้ภาษาต่างประเทศด้วย ต้องมีความหมายตรงกับภาษาไทยที่กำหนดไว้ข้างต้น หรือในกรณีที่ใช้เฉพาะภาษาต่างประเทศเพื่อการส่งออก

8. การชักตัวอย่างและเกณฑ์ตัดสิน

8.1 การชักตัวอย่างและเกณฑ์ตัดสินให้เป็นไปตามภาคผนวก ก.

9. การทดสอบ

9.1 ให้ใช้วิธีทดสอบที่กำหนดในมาตรฐานนี้หรือวิธีอื่นใดที่ให้ผลเทียบเท่า ในกรณีที่มีข้อโต้แย้งให้ใช้วิธีที่กำหนดในมาตรฐานนี้

9.2 ความถี่ในการทดสอบประจำของผู้ทำ แนะนำให้เป็นไปตามภาคผนวก ข.

9.3 จุลินทรีย์

9.3.1 โคลิฟอร์มแบคทีเรีย ให้ปฏิบัติตาม Standard Methods for the Examination of Water and Wastewater 20th Edition 1998 ข้อ 9221C

9.3.2 *เอสเชอริเชีย โคไล* ให้ปฏิบัติตาม Standard Methods for the Examination of Water and Wastewater 20th Edition 1998 ข้อ 9221F

9.3.3 *สตาฟิโลคอกคัส ออเรียส* ให้ปฏิบัติตาม Standard Methods for the Examination of Water and Wastewater 20th Edition 1998 ข้อ 9213B ข้อย่อย 7

9.3.4 *ซาลโมเนลลา* ให้ปฏิบัติตาม Standard Methods for the Examination of Water and Wastewater 20th Edition 1998 ข้อ 9260B

9.3.5 *คลอสตริเดียม เพอร์ฟริงเจนส์* ให้ปฏิบัติตาม COMPENDIUM OF METHODS FOR THE MICROBIOLOGICAL EXAMINATION OF FOODS 4th EDITION 2001 หน้า 325 ถึง 330

ภาคผนวก ก.

การชักตัวอย่างและเกณฑ์ตัดสิน

(ข้อ 8.1)

ก.1 ประเภทที่ 1

ก.1.1 รุ่น ในที่นี้ หมายถึง น้ำบริโภคที่บรรจุในภาชนะบรรจุชนิดและขนาดเดียวกัน ในวันเดียวกันหรือระยะเวลาเดียวกันอย่างต่อเนื่อง

ก.1.2 การชักตัวอย่างและการยอมรับ ให้เป็นไปตามแผนการชักตัวอย่างที่กำหนดต่อไปนี้ หรืออาจใช้แผนการชักตัวอย่างอื่นที่เทียบเท่ากันทางวิชาการกับแผนที่กำหนดไว้

ก.1.2.1 การชักตัวอย่างและการยอมรับสำหรับการทดสอบการบรรจุและเครื่องหมายและฉลาก

(1) ให้ชักตัวอย่างโดยวิธีสุ่มจากรุ่นเดียวกันตามจำนวนที่กำหนดในตารางที่ ก.1

(2) จำนวนตัวอย่างน้ำบริโภคที่ไม่เป็นไปตามข้อ 6. และข้อ 7. ต้องไม่เกินเลขจำนวนที่ยอมรับที่กำหนดในตารางที่ ก.1 จึงจะถือว่าน้ำบริโภครุ่นนั้นเป็นไปตามเกณฑ์ที่กำหนด

ตารางที่ ก.1 แผนการชักตัวอย่างสำหรับการทดสอบการบรรจุและเครื่องหมายและฉลาก

(ข้อ ก.1.2.1)

ขนาดรุ่น หน่วยภาชนะบรรจุ	ขนาดตัวอย่าง หน่วยภาชนะบรรจุ	เลขจำนวนที่ยอมรับ
ไม่เกิน 10 000	8	1
10 001 ถึง 35 000	13	2
35 001 ถึง 150 000	20	3
150 001 ถึง 500 000	32	5
มากกว่า 500 000 ขึ้นไป	50	7

ก.1.2.2 การชักตัวอย่างและการยอมรับสำหรับการทดสอบคุณลักษณะที่ต้องการ

(1) ให้ใช้ตัวอย่างที่ผ่านการทดสอบตามข้อ ก.1.2.1 แล้วแบ่งตัวอย่างมาภาชนะบรรจุละเท่า ๆ กัน นำมาผสมรวมกันเป็นตัวอย่างรวม โดยมีปริมาตรรวมไม่น้อยกว่า 4 ลูกบาศก์เดซิเมตร ในกรณีที่ตัวอย่างไม่พอให้ชักตัวอย่างเพิ่มจนได้ปริมาตรรวมตามที่กำหนด

(2) ตัวอย่างต้องเป็นไปตามข้อ 4.1 ข้อ 4.2 ข้อ 4.3 และข้อ 4.4 จึงจะถือว่าน้ำบริโภครุ่นนั้นเป็นไปตามเกณฑ์ที่กำหนด

ก.1.2.3 การชักตัวอย่างและการยอมรับสำหรับการทดสอบจุลินทรีย์

(1) ให้ชักตัวอย่างโดยวิธีสุ่มจากรุ่นเดียวกันจำนวน 3 หน่วยภาชนะบรรจุ

(2) ตัวอย่างทุกตัวอย่างต้องเป็นไปตามข้อ 5.2 จึงจะถือว่าน้ำบริโภครุ่นนั้นเป็นไปตามเกณฑ์ที่กำหนด

ก.1.3 เกณฑ์ตัดสิน

ตัวอย่างน้ำบริโภคต้องเป็นไปตามข้อ ก.1.2.1(2) ข้อ ก.1.2.2(2) และข้อ ก.1.2.3(2) ทุกข้อ จึงจะถือว่าน้ำบริโภครุ่นนั้นเป็นไปตามมาตรฐานผลิตภัณฑ์อุตสาหกรรมนี้

ก.2 ประเภทที่ 2

ก.2.1 การชักตัวอย่างและการยอมรับให้เป็นไปตามแผนการชักตัวอย่างที่กำหนดต่อไปนี้ หรืออาจใช้แผนการชักตัวอย่างอื่นที่เทียบเท่ากันทางวิชาการกับแผนที่กำหนดไว้

ก.2.1.1 การชักตัวอย่างและการยอมรับสำหรับการทดสอบคุณลักษณะที่ต้องการ

(1) ให้ชักตัวอย่างน้ำบริโภคก่อนเข้าสู่ระบบท่อจ่ายไม่น้อยกว่า 6 ลูกบาศก์เดซิเมตร แล้วเก็บในภาชนะที่สะอาดและปิดได้สนิท

(2) ตัวอย่างต้องเป็นไปตามข้อ 4.1 ข้อ 4.2 ข้อ 4.3 และข้อ 4.4 จึงจะถือว่าน้ำบริโภครุ่นนั้นเป็นไปตามเกณฑ์ที่กำหนด

ก.2.1.2 การชักตัวอย่างและการยอมรับสำหรับการทดสอบจุลินทรีย์

ให้ชักตัวอย่างน้ำบริโภคในระบบท่อจ่ายตามตารางที่ ก.2 และระวังการปนเปื้อนโดยปฏิบัติดังนี้

(1) ภาชนะที่ใช้เก็บตัวอย่างให้ใช้ขวดแก้วปากกว้างชนิดทนความร้อนที่มีจุกแก้วปิดได้สนิท ความจุประมาณ 170 ลูกบาศก์เซนติเมตร ใส่สารละลายโซเดียมไทโอซัลเฟต ร้อยละ 3 โดยน้ำหนัก จำนวน 0.1 ลูกบาศก์เซนติเมตร ลงในขวดแก้ว หุ้มด้วยกระดาษหรืออะลูมิเนียมเปลว นำขวดแก้วใส่ลงในกระบอกโลหะ แล้วนำไปอบในตู้อบที่อุณหภูมิ 160 องศาเซลเซียสถึง 170 องศาเซลเซียส เป็นเวลา 1 ชั่วโมง ให้ปิดจุกแก้วไว้ตลอดจนกว่าจะเก็บตัวอย่าง การเปิดให้จับจุกแก้วเฉพาะส่วนบน ห้ามจับส่วนที่จะปิดลงในขวดแก้วและคอขวด

(2) ใช้ไฟจากตะเกียงแอลกอฮอล์ลนปากก๊อกน้ำให้ร้อนเพื่อฆ่าเชื้อโรค แล้วปิดน้ำให้ไหลเต็มที่โดยปล่อยทิ้งไป 5 นาทีเพื่อทำความสะอาดปากก๊อกน้ำ ใช้ไฟลนปากขวดพร้อมทั้งจุกจนร้อน เปิดจุกขวดออกรองรับน้ำบริโภคประมาณ 2 ใน 3 ส่วนของความจุขวด (ประมาณ 100 ลูกบาศก์เซนติเมตร) อย่าให้น้ำบริโภคเต็มขวด เพื่อเหลือที่ว่างไว้สำหรับเขย่าตัวอย่างให้เข้ากันขณะทดสอบ ในการเก็บน้ำนี้ไม่ควรจับคอขวด เมื่อเปิดจุกขวดออกต้องถือจุกไว้อย่างให้สัมผัสกับสิ่งอื่น ก่อนปิดจุกขวดให้ใช้ไฟลนปากขวดและจุกอีกครั้ง ใส่ขวดเก็บตัวอย่างนี้ลงในกระบอกโลหะแล้วปิดฝาไว้ การทดสอบให้ทำทันที หากจำเป็นให้ทดสอบภายในเวลาไม่เกิน 30 ชั่วโมง หลังจากเก็บตัวอย่างโดยเก็บรักษาตัวอย่างไว้ที่อุณหภูมิไม่เกิน 10 องศาเซลเซียส

ตารางที่ ก.2 การชักตัวอย่างและการยอมรับสำหรับการทดสอบจุลินทรีย์

(ข้อ ก.2.1.2)

จำนวนประชากรที่ใช้น้ำ (คน)	อย่างน้อยต้องวิเคราะห์ทุกช่วงเวลา	จำนวนตัวอย่างจากระบบท่อจ่ายในแต่ละเดือน
ไม่เกิน 20 000	1 เดือน	1 ตัวอย่างต่อประชากร 5 000 คน
20 000 ถึง 50 000	2 สัปดาห์	1 ตัวอย่างต่อประชากร 5 000 คน
50 000 ถึง 100 000	4 วัน	1 ตัวอย่างต่อประชากร 5 000 คน
100 001 ขึ้นไป	1 วัน	1 ตัวอย่างต่อประชากร 10 000 คน

ก.2.1.3 ตัวอย่างต้องเป็นไปตามข้อ 5.2 จึงจะถือว่าน้ำบริโภครุ่นนั้นเป็นไปตามเกณฑ์ที่กำหนด

ก.2.2 เกณฑ์ตัดสิน

ตัวอย่างน้ำบริโภคต้องเป็นไปตามข้อ ก.2.1.1(2) และข้อ ก.2.1.3 ทุกข้อ จึงจะถือว่าน้ำบริโภครุ่นนั้นเป็นไปตามมาตรฐานผลิตภัณฑ์อุตสาหกรรมนี้

ภาคผนวก ข.

ความถี่ในการทดสอบประจำ

(ข้อ 9.2)

กลุ่มที่ 1 ตรวจสอบทุกวัน	กลุ่มที่ 2 ตรวจอย่างน้อยปีละ 2 ครั้ง ยกเว้นจุลินทรีย์ตรวจทุก 2 เดือน	กลุ่มที่ 3 ตรวจปีละครั้ง
1. สี กลิ่นและรส	1. สี กลิ่นและรส	1. ทองแดง
2. ความขุ่น	2. ความขุ่น	2. สังกะสี
3. ค่าความเป็นกรด-ด่าง	3. ค่าความเป็นกรด-ด่าง	3. ปรอท
4. โคลิฟอร์ม	4. ปริมาณสารที่ละลายทั้งหมด	4. ตะกั่ว
5. จุลินทรีย์ทั้งหมด (ต้องไม่มากกว่า 500 CFU)	5. แมงกานีส	5. แคดเมียม
6. ปริมาณสารที่ละลายทั้งหมด	6. ซัลเฟต	6. แบเรียม
	7. คลอไรด์	7. โครเมียม
	8. ฟลูออไรด์	8. ซีลีเนียม
	9. ความกระด้างทั้งหมด	9. สารหนู
	10. จุลินทรีย์	10. เหล็ก
		11.ไซยาไนด์
		12.ลีเนียร์อัลคิลเบนซีนซัลโฟเนต
		13.ฟีนอลิกซับสแตนซ์

ประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ
ฉบับที่ ๑๐ (พ.ศ. ๒๕๓๘)
ออกตามความในพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕
เรื่อง กำหนดมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป

อาศัยอำนาจตามความในมาตรา ๓๒ แห่งพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ คณะกรรมการสิ่งแวดล้อมแห่งชาติกำหนดมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป ไว้ดังต่อไปนี้

ข้อ ๑ ในประกาศนี้

"เครื่องวัด ระบบนันดีสเปอร์ซีฟ อินฟราเรด ดีเทคชั่น (Non- dispersive Infrared Detection)" หมายความว่า เครื่องมือวัดค่าก๊าซคาร์บอนมอนอกไซด์โดยใช้รังสีอินฟราเรด

"เครื่องวัดระบบเคมีลูมิเนสเซน (Chemiluminescence)" หมายความว่า

(๑) เครื่องมือวัดค่าก๊าซไนโตรเจนไดออกไซด์โดยใช้ก๊าซโอโซนทำปฏิกิริยากับก๊าซไนตริกออกไซด์ ซึ่งถูกเปลี่ยนมาจากก๊าซไนโตรเจนไดออกไซด์แล้ววัดความเข้มของแสงซึ่งเกิดจากปฏิกิริยานั้น ณ ที่ความยาวคลื่นที่สูงกว่า ๖๐๐ นาโนมิเตอร์ (Nanometer) หรือ

(๒) เครื่องมือวัดค่าก๊าซโอโซนโดยใช้ก๊าซเอธีลีนทำปฏิกิริยากับก๊าซโอโซนแล้ววัดความเข้มของแสงซึ่งเกิดจากปฏิกิริยานั้น ณ ที่ความยาวคลื่นระหว่าง ๓๕๐ ถึง ๕๕๐ นาโนมิเตอร์

"ระบบพาราโรซานิลีน (Pararosaniline)" หมายความว่า การวัดค่าก๊าซซัลเฟอร์ไดออกไซด์ โดยการดูดอากาศผ่านสารละลายโปตัสเซียม เตตราคลอโรเมอคิวเรต (Potassium Tetrachloromercurate) เกิดเป็นสารไดคลอโรซัลไฟโตเมอคิวเรต คอมเพลกซ์

(Dichlorosulfito Mercurate Complex) ทำปฏิกิริยากับสารพาราโรซานิลีนและฟอร์มาลดีไฮด์ (Pararosaniline and Formaldehyde) เกิดเป็นสีของพาราโรซานิลีนเมธิล ซัลฟอนิก แอซิด (Pararosaniline Methyl Sulfonic Acid) ซึ่งจะถูกวัดความสามารถในการดูดซึมแสง ณ ที่ช่วงคลื่น ๕๔๘ นาโนมิเตอร์

"เครื่องวัดระบบอะตอมมิก แอบซอพชั่น สเปคโตรมิเตอร์ (Atomic Absorption Spectrometer)" หมายความว่า เครื่องมือวัดปริมาณของตะกั่ว โดยใช้เปลวไฟอะเซทีลีน (Acetylene Flame) ที่ความยาวคลื่น ๒๘๓.๓ หรือ ๒๑๗ นาโนมิเตอร์

"ระบบกราวิเมตริก (Gravimetric)" หมายความว่า การวัดค่าฝุ่นละอองโดยดูดอากาศผ่านแผ่นกรอง ซึ่งมีประสิทธิภาพในการกรองฝุ่นละอองขนาด ๐.๓ ไมครอน (Micron) ได้ร้อยละ ๙๙ แล้วหาน้ำหนักฝุ่นละอองจากแผ่นกรองนั้น

ข้อ ๒ ค่าก๊าซในบรรยากาศโดยทั่วไปในช่วงเวลาหนึ่งเวลาใดให้เป็นไปดังต่อไปนี้

(๑) ค่าเฉลี่ยของก๊าซคาร์บอนมอนอกไซด์ในเวลา ๑ ชั่วโมง จะต้องไม่เกิน ๓๐ ส่วนในล้านส่วน (ppm) หรือไม่เกิน ๓๔.๒ มิลลิกรัมต่อลูกบาศก์เมตรและในเวลา ๘ ชั่วโมง จะต้องไม่เกิน ๙ ส่วนในล้านส่วน หรือไม่เกิน ๑๐.๒๖ มิลลิกรัมต่อลูกบาศก์เมตร

(๒) ค่าเฉลี่ยของก๊าซไนโตรเจนไดออกไซด์ในเวลา ๑ ชั่วโมง จะต้องไม่เกิน ๐.๑๗ ส่วนในล้านส่วน หรือไม่เกิน ๐.๓๒ มิลลิกรัมต่อลูกบาศก์เมตร

(๓) ค่าเฉลี่ยของก๊าซโอโซนในเวลา ๑ ชั่วโมง จะต้องไม่เกิน ๐.๑๐ ส่วนในล้านส่วน หรือไม่เกิน ๐.๒๐ มิลลิกรัมต่อลูกบาศก์เมตร

(๔) ค่าเฉลี่ยของก๊าซซัลเฟอร์ไดออกไซด์ในเวลา ๒๔ ชั่วโมง จะต้องไม่เกิน ๐.๑๒ ส่วนในล้านส่วน หรือไม่เกิน ๐.๓๐ มิลลิกรัมต่อลูกบาศก์เมตร และค่ามัชฌิมเรขาคณิต (Geometric Mean) ในเวลา ๑ ปี จะต้องไม่เกิน ๐.๐๔ ส่วนในล้านส่วน หรือไม่เกิน ๐.๑๐ มิลลิกรัมต่อลูกบาศก์เมตร

ข้อ ๓ การคำนวณค่าความเข้มข้นของก๊าซแต่ละชนิดในบรรยากาศโดยทั่วไปให้คำนวณเทียบที่ความดัน ๑ บรรยากาศ และอุณหภูมิ ๒๕ องศาเซลเซียส

ข้อ ๔ ค่าสารในบรรยากาศโดยทั่วไป ในช่วงเวลาหนึ่งเวลาใดให้เป็นไปดังต่อไปนี้

(๑) ค่าเฉลี่ยของตะกั่วในเวลา ๑ เดือน จะต้องไม่เกิน ๑.๕ ไมโครกรัมต่อลูกบาศก์เมตร

(๒) ค่าเฉลี่ยของฝุ่นละอองขนาดไม่เกิน ๑๐ ไมครอน ในเวลา ๒๔ ชั่วโมง จะต้องไม่เกิน ๐.๑๒ มิลลิกรัมต่อลูกบาศก์เมตร และค่ามัชฌิมเรขาคณิตของสารดังกล่าวในเวลา ๑ ปี จะต้องไม่เกิน ๐.๑๕ มิลลิกรัมต่อลูกบาศก์เมตร

(๓) ค่าเฉลี่ยของฝุ่นละอองรวมหรือฝุ่นละอองขนาดไม่เกิน ๑๐๐ ไมครอน ในเวลา ๒๔ ชั่วโมง จะต้องไม่เกิน ๐.๓๓ มิลลิกรัมต่อลูกบาศก์เมตร และค่ามัชฌิมเรขาคณิตของสารดังกล่าวในเวลา ๑ ปี จะต้องไม่เกิน ๐.๑๐ มิลลิกรัมต่อลูกบาศก์เมตร

ข้อ ๕ การวัดหาค่าเฉลี่ยของก๊าซคาร์บอนมอนอกไซด์ในเวลา ๑ ชั่วโมงหรือในเวลา ๘ ชั่วโมง ให้ใช้เครื่องวัดระบบนันดีสเปอร์ซีพ อินฟราเรด ดีเทคชั่น หรือระบบอื่นที่กรมควบคุมมลพิษให้ความเห็นชอบ

ข้อ ๖ การวัดหาค่าเฉลี่ยของก๊าซไนโตรเจนไดออกไซด์หรือก๊าซโอโซนในเวลา ๑ ชั่วโมง ให้ใช้เครื่องวัดระบบเคมีลูมิเนสเซน หรือระบบอื่นที่กรมควบคุมมลพิษให้ความเห็นชอบ

ข้อ ๗ การวัดหาค่าเฉลี่ยของก๊าซซัลเฟอร์ไดออกไซด์ในเวลา ๒๔ ชั่วโมง หรือในเวลา ๑ ปี ให้ใช้วิธีการวัดตามระบบพาราโรซานิลีน หรือระบบอื่นที่กรมควบคุมมลพิษให้ความเห็นชอบ

ข้อ ๘ การวัดหาค่าเฉลี่ยของตะกั่วในเวลา ๑ เดือน ให้เก็บอากาศผ่านแผ่นกรองในเครื่องเก็บตัวอย่างอากาศชนิดไฮโวลุม (High Volume-Air Sampler) สกัดตะกั่วออกจากแผ่นกรองโดยใช้กรดดินประสิวและกรดเกลือ แล้วนำไปวัดค่าของตะกั่วโดยใช้เครื่องวัดระบบอะตอมมิก แอบซอพชั่น สเปคโตรมิเตอร์ หรือระบบอื่นที่กรมควบคุมมลพิษให้ความเห็นชอบ

ข้อ ๙ การวัดหาค่าเฉลี่ยของฝุ่นละอองรวมหรือฝุ่นละอองขนาดไม่เกิน ๑๐ ไมครอน ในเวลา ๒๔ ชั่วโมง หรือในเวลา ๑ ปี ให้ใช้วิธีการวัดตามระบบกราวิเมตริก หรือระบบอื่นที่กรมควบคุมมลพิษให้ความเห็นชอบ

ข้อ ๑๐ การวัดหาค่าเฉลี่ยของก๊าซหรือสารอย่างหนึ่งอย่างใดตามข้อ ๕ ถึงข้อ ๗ ให้ทำในบรรยากาศทั่วๆ ไป และต้องสูงจากพื้นดินอย่างน้อย ๓ เมตร แต่ไม่เกิน ๖ เมตร

การวัดหาค่าเฉลี่ยของตะกั่วและฝุ่นละอองตามข้อ ๘ และข้อ ๙ ให้ทำในบรรยากาศทั่วๆ ไป และต้องสูงจากพื้นดินอย่างน้อย ๑.๕๐ เมตร แต่ไม่เกิน ๖ เมตร

ประกาศ ณ วันที่ ๑๗ เมษายน พ.ศ. ๒๕๓๘
ชวน หลีกภัย
นายกรัฐมนตรี
ประธานคณะกรรมการสิ่งแวดล้อมแห่งชาติ

(ประกาศในราชกิจจานุเบกษา เล่ม ๑๑๒ ตอนที่ ๔๒ ง วันที่ ๒๕ พฤษภาคม ๒๕๓๘)

แก้คำผิด

ประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ
ฉบับที่ ๑๐ (พ.ศ. ๒๕๓๘) ออกตามความในพระราชบัญญัติส่งเสริมและรักษา
คุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕

เรื่อง กำหนดมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป
ซึ่งประกาศในราชกิจจานุเบกษา
ฉบับประกาศทั่วไป เล่ม ๑๑๒ ตอนที่ ๔๒ ง ลงวันที่ ๒๕ พฤษภาคม ๒๕๓๘
หน้า ๙๑ บรรทัดที่ ๑๙ คำว่า
"ไม่เกิน ๐.๑๕ มิลลิกรัม" ให้แก้เป็น
"ไม่เกิน ๐.๐๕ มิลลิกรัม"

(ประกาศในราชกิจจานุเบกษา เล่ม ๑๑๒ ตอนที่ ๗๑ ง วันที่ ๕ กันยายน ๒๕๓๘)

ประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ
ฉบับที่ ๒๑ (พ.ศ. ๒๕๔๔)
ออกตามความในพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕
เรื่อง กำหนดมาตรฐานค่าก๊าซซัลเฟอร์ไดออกไซด์ในบรรยากาศโดยทั่วไป ในเวลา ๑ ชั่วโมง

อาศัยอำนาจตามความในมาตรา ๓๒ และมาตรา ๓๔ แห่งพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ คณะกรรมการสิ่งแวดล้อมแห่งชาติ จึงปรับปรุงแก้ไขมาตรฐานค่าก๊าซซัลเฟอร์ไดออกไซด์ในบรรยากาศโดยทั่วไปในเวลา ๑ ชั่วโมง ไว้ดังต่อไปนี้

(๑) ให้ยกเลิกข้อ ๒ แห่งประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ ฉบับที่ ๑๒ (พ.ศ. ๒๕๓๘) ออกตามความในพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ เรื่อง กำหนดมาตรฐานค่าก๊าซซัลเฟอร์ไดออกไซด์ในบรรยากาศโดยทั่วไปในเวลา ๑ ชั่วโมง

(๒) ให้ยกเลิกความในข้อ ๓ และข้อ ๕ แห่งประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ ฉบับที่ ๑๒ (พ.ศ. ๒๕๓๘) ออกตามความในพระราชบัญญัติส่งเสริมและรักษา คุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ เรื่อง กำหนดมาตรฐานค่าก๊าซซัลเฟอร์ไดออกไซด์ในบรรยากาศโดยทั่วไปในเวลา ๑ ชั่วโมง และให้ใช้ความต่อไปนี้แทน

“ข้อ ๓ ค่าเฉลี่ยความเข้มข้นของก๊าซซัลเฟอร์ไดออกไซด์ในบรรยากาศโดยทั่วไปในเวลา ๑ ชั่วโมง จะต้องไม่เกิน ๐.๓๐ ส่วนในล้านส่วน (ppm) หรือไม่เกิน ๗๘๐ ไมโครกรัมต่อลูกบาศก์เมตร”

“ข้อ ๕ การวัดหาค่าเฉลี่ยความเข้มข้นของก๊าซซัลเฟอร์ไดออกไซด์ในบรรยากาศโดยทั่วไปในเวลา ๑ ชั่วโมง ตามข้อ ๓ ให้ใช้เครื่องวัดระบบ ยูวี ฟลูออเรสเซน หรือระบบอื่นที่กรมควบคุมมลพิษประกาศในราชกิจจานุเบกษา”

ประกาศ ณ วันที่ ๙ เมษายน พ.ศ. ๒๕๔๔

(นายเดช บุญ-หลง)

รองนายกรัฐมนตรี ปฏิบัติหน้าที่

ประธานคณะกรรมการสิ่งแวดล้อมแห่งชาติ

(ประกาศในราชกิจจานุเบกษา เล่ม ๑๑๘ ตอนพิเศษ ๓๙ ง ลงวันที่ ๓๐ เมษายน ๒๕๔๔)

ประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ
ฉบับที่ ๒๔ (พ.ศ. ๒๕๔๗)
เรื่อง กำหนดมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป

อาศัยอำนาจตามความในมาตรา ๓๒ และมาตรา ๓๔ แห่งพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ อันเป็นพระราชบัญญัติที่มีบทบัญญัติบางประการเกี่ยวกับการจำกัดสิทธิและเสรีภาพของบุคคล ซึ่งมาตรา ๒๙ ประกอบกับมาตรา ๓๕ มาตรา ๔๘ มาตรา ๕๐ และมาตรา ๕๑ ของรัฐธรรมนูญแห่งราชอาณาจักรไทยบัญญัติให้กระทำได้โดยอาศัยอำนาจตามบทบัญญัติแห่งกฎหมาย คณะกรรมการสิ่งแวดล้อมแห่งชาติ จึงได้มีมติในคราวการประชุมครั้งที่ ๒/๒๕๔๗ เมื่อวันที่ ๒๔ กุมภาพันธ์ ๒๕๔๗ ให้ปรับปรุงแก้ไขมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป ดังต่อไปนี้

ข้อ ๑ ให้ยกเลิกความใน (๔) ของข้อ ๒ แห่งประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ ฉบับที่ ๑๐ (พ.ศ. ๒๕๓๘) ออกตามความในพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ เรื่อง กำหนดมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป และให้ใช้ความต่อไปนี้แทน

“(๔) ค่าเฉลี่ยของก๊าซซัลเฟอร์ไดออกไซด์ ในเวลา ๒๔ ชั่วโมง จะต้องไม่เกิน ๐.๑๒ ส่วนในล้านส่วน หรือไม่เกิน ๐.๓๐ มิลลิกรัมต่อลูกบาศก์เมตร และค่ามัชฌิมเลขคณิต (Arithmetic Mean) ในเวลา ๑ ปี จะต้องไม่เกิน ๐.๐๔ ส่วนในล้านส่วน หรือไม่เกิน ๐.๑๐ มิลลิกรัมต่อลูกบาศก์เมตร”

ข้อ ๒ ให้ยกเลิกความใน (๒) และ (๓) ของข้อ ๔ แห่งประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ ฉบับที่ ๑๐ (พ.ศ. ๒๕๓๘) ออกตามความในพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ เรื่อง กำหนดมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป และให้ใช้ความต่อไปนี้แทน

“(๒) ค่าเฉลี่ยของฝุ่นละอองขนาดไม่เกิน ๑๐ ไมครอน ในเวลา ๒๔ ชั่วโมง จะต้องไม่เกิน ๐.๑๒ มิลลิกรัมต่อลูกบาศก์เมตร และค่ามัชฌิมเลขคณิต (Arithmetic Mean) ในเวลา ๑ ปี จะต้องไม่เกิน ๐.๐๕ มิลลิกรัมต่อลูกบาศก์เมตร

(๓) ค่าเฉลี่ยของฝุ่นละอองรวมหรือฝุ่นละอองขนาดไม่เกิน ๑๐๐ ไมครอน ในเวลา ๒๔ ชั่วโมง จะต้องไม่เกิน ๐.๓๓ มิลลิกรัมต่อลูกบาศก์เมตร และค่ามัชฌิมเลขคณิต (Arithmetic Mean) ในเวลา ๑ ปี จะต้องไม่เกิน ๐.๑๐ มิลลิกรัมต่อลูกบาศก์เมตร”

ประกาศ ณ วันที่ ๙ สิงหาคม พ.ศ. ๒๕๔๗

(ลงนาม) *จาตุรนต์ ฉายแสง*

(นายจาตุรนต์ ฉายแสง)

รองนายกรัฐมนตรี

ปฏิบัติหน้าที่ประธานคณะกรรมการสิ่งแวดล้อมแห่งชาติ

ราชกิจจานุเบกษา ฉบับประกาศทั่วไป เล่ม ๑๒๑ ตอนพิเศษ ๑๐๔ ง วันที่ ๒๒ กันยายน ๒๕๔๗

ประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ

ฉบับที่ ๓๓ (พ.ศ. ๒๕๕๒)

เรื่อง กำหนดมาตรฐานค่าก๊าซไนโตรเจนไดออกไซด์ในบรรยากาศโดยทั่วไป

โดยที่เป็นการสมควรกำหนดมาตรฐานค่าก๊าซไนโตรเจนไดออกไซด์ในบรรยากาศโดยทั่วไป เพื่อเป็นเกณฑ์ทั่วไปสำหรับการส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมตามพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕

อาศัยอำนาจตามความในมาตรา ๓๒ (๔) และมาตรา ๓๔ แห่งพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ อันเป็นพระราชบัญญัติที่มีบทบัญญัติบางประการเกี่ยวกับการจำกัดสิทธิและเสรีภาพของบุคคล ซึ่งมาตรา ๒๙ ประกอบกับมาตรา ๓๓ มาตรา ๓๘ มาตรา ๔๑ และมาตรา ๔๓ ของรัฐธรรมนูญแห่งราชอาณาจักรไทย บัญญัติให้กระทำได้โดยอาศัยอำนาจตามบทบัญญัติแห่งกฎหมาย คณะกรรมการสิ่งแวดล้อมแห่งชาติจึงออกประกาศกำหนดมาตรฐานค่าก๊าซไนโตรเจนไดออกไซด์ในบรรยากาศโดยทั่วไปไว้ ดังต่อไปนี้

ข้อ ๑ ในประกาศนี้

“เครื่องวัดระบบเคมีลูมิเนสเซน” (Chemiluminescence) หมายความว่า เครื่องมือวัดค่าก๊าซไนโตรเจนไดออกไซด์โดยใช้ก๊าซโอโซนทำปฏิกิริยากับก๊าซไนตริกออกไซด์ซึ่งถูกเปลี่ยนมาจากก๊าซไนโตรเจนไดออกไซด์แล้ววัดความเข้มของแสงซึ่งเกิดจากปฏิกิริยานั้น ณ ที่ความยาวคลื่นที่สูงกว่า ๖๐๐ นาโนมิเตอร์ (Nanometer)

ข้อ ๒ ให้ยกเลิก

(๑) ความใน (๒) ของข้อ ๒ แห่งประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ ฉบับที่ ๑๐ (พ.ศ. ๒๕๓๘) ออกตามความในพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ เรื่อง กำหนดมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป

(๒) ความใน (๑) ของข้อ ๖ แห่งประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ ฉบับที่ ๑๐ (พ.ศ. ๒๕๓๘) ออกตามความในพระราชบัญญัติส่งเสริมและรักษาคุณภาพสิ่งแวดล้อมแห่งชาติ พ.ศ. ๒๕๓๕ เรื่อง กำหนดมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป แก้ไขเพิ่มเติมโดยประกาศคณะกรรมการสิ่งแวดล้อมแห่งชาติ ฉบับที่ ๒๘ (พ.ศ. ๒๕๕๐) เรื่อง กำหนดมาตรฐานคุณภาพอากาศในบรรยากาศโดยทั่วไป

ข้อ ๓ ให้กำหนดมาตรฐานค่าก๊าซไนโตรเจนไดออกไซด์ในบรรยากาศโดยทั่วไปไว้ดังต่อไปนี้

(๑) ค่าเฉลี่ยของก๊าซไนโตรเจนไดออกไซด์ในเวลา ๑ ชั่วโมง จะต้องไม่เกิน ๐.๑๗ ส่วนในล้านส่วนหรือไม่เกิน ๐.๓๒ มิลลิกรัมต่อลูกบาศก์เมตร

(๒) ค่ามัชฌิมเลขคณิต (Arithmetic Mean) ของก๊าซไนโตรเจนไดออกไซด์ในเวลา ๑ ปี จะต้องไม่เกิน ๐.๐๓ ส่วนในล้านส่วน หรือไม่เกิน ๐.๐๕๗ มิลลิกรัมต่อลูกบาศก์เมตร

ข้อ ๔ การคำนวณค่าความเข้มข้นของก๊าซไนโตรเจนไดออกไซด์ในบรรยากาศโดยทั่วไป ให้คำนวณเทียบที่ความดัน ๑ บรรยากาศ และอุณหภูมิ ๒๕ องศาเซลเซียส

ข้อ ๕ การวัดค่าเฉลี่ยของก๊าซไนโตรเจนไดออกไซด์ในเวลา ๑ ชั่วโมง หรือค่ามัชฌิมเลขคณิต (Arithmetic Mean) ในเวลา ๑ ปี ให้ใช้เครื่องวัดระบบเคมีลูมิเนสเซน หรือระบบอื่นที่กรมควบคุมมลพิษให้ความเห็นชอบ

ประกาศ ณ วันที่ ๑๗ มิถุนายน พ.ศ. ๒๕๕๒
อภิสิทธิ์ เวชชาชีวะ
นายกรัฐมนตรี
ประธานกรรมการสิ่งแวดล้อมแห่งชาติ

คำแนะนำของคณะกรรมการสาธารณสุข

ฉบับที่ 1 / 2550

เรื่อง การควบคุมการประกอบกิจการสระว่ายน้ำ หรือกิจการอื่นๆ ในทำนองเดียวกัน

****

การประกอบกิจการสระว่ายน้ำ หรือกิจการอื่นๆ ในทำนองเดียวกัน เป็นกิจการที่ถูกควบคุมในลักษณะที่เป็นกิจการที่เป็นอันตรายต่อสุขภาพ ตามมาตรา 31 แห่งพระราชบัญญัติการสาธารณสุข พ.ศ. 2535 ซึ่งการประกอบกิจการนี้เป็นแหล่งที่ผู้ใช้บริการเข้ามาชุมนุมอยู่รวมกันในสระว่ายน้ำ สวนน้ำ สวนสนุกที่มีลักษณะเช่นเดียวกับสระว่ายน้ำ อันอาจก่อให้เกิดผลกระทบต่อสุขภาพของประชาชน เนื่องจากมีการก่อสร้างสระว่ายน้ำ หรือกิจการอื่นๆ ในทำนองเดียวกันเพิ่มมากขึ้น ทั้งสโมสร สมาคม สถานศึกษา สวนสนุก และชุมชนในท้องถิ่นทั่วไป ซึ่งถ้าสระว่ายน้ำเหล่านี้ขาดการดูแลและบำรุงรักษาตามหลักสุขาภิบาล การอนามัยสิ่งแวดล้อม การดูแลคุณภาพน้ำ รวมทั้งมาตรการด้านความปลอดภัยอย่างถูกต้อง สระว่ายน้ำอาจกลายเป็นแหล่งแพร่เชื้อโรคต่างๆ ได้ เช่น โรคเยื่อตาอักเสบ หูอักเสบ โรคผิวหนัง โรคระบบทางเดินหายใจ โรคระบบทางเดินอาหาร รวมทั้งโรคไม่ติดเชื้อต่างๆ อันมีผลมาจากการใช้สารเคมี เช่น อาการผิวหนังเนื่องจากแพ้สารเคมี อาการเจ็บคอ ไอ แน่นหน้าอก อาการคลื่นไส้อาเจียน เนื่องจากแพ้สารเคมี นอกจากนั้นยังรวมถึงอุบัติเหตุต่างๆ ด้วย

อาศัยอำนาจตามความในมาตรา 10(3) แห่งพระราชบัญญัติการสาธารณสุข พ.ศ. 2535คณะกรรมการสาธารณสุขจึงได้มีมติในคราวการประชุมครั้งที่ 43-3/2549 เมื่อวันที่ 27 มิถุนายน 2549 เห็นชอบให้ออกคำแนะนำแก่ราชการส่วนท้องถิ่นในการออกข้อกำหนดท้องถิ่นเกี่ยวกับหลักเกณฑ์ในการควบคุมกำกับดูแลการประกอบกิจการสระว่ายน้ำหรือกิจการอื่นในทำนองเดียวกัน ดังต่อไปนี้

ข้อ 1 กรณีที่ในเขตราชการส่วนท้องถิ่นใด มีการประกอบกิจการสระว่ายน้ำและกิจการอื่นในทำนองเดียวกัน ราชการส่วนท้องถิ่นนั้นอาจออกข้อกำหนดของท้องถิ่นกำหนดให้กิจการดังกล่าว เป็นกิจการที่ต้องควบคุมในท้องถิ่นนั้นได้ ตามมาตรา 32 (1) แห่งพระราชบัญญัติการสาธารณสุข พ.ศ. 2535

ข้อ 2 เพื่อประโยชน์ในการควบคุมหรือกำกับดูแลสถานประกอบกิจการสระว่ายน้ำหรือกิจการอื่นๆ ในทำนองเดียวกัน ราชการส่วนท้องถิ่นอาจพิจารณาออกข้อกำหนดของท้องถิ่น กำหนดหลักเกณฑ์ และเงื่อนไขทั่วไป ให้ผู้ดำเนินกิจการปฏิบัติเกี่ยวกับสภาพหรือสุขลักษณะของสถานที่ที่ใช้ในการประกอบกิจการ และมาตรการป้องกันอันตรายต่อสุขภาพ ตามมาตรา 32(2) แห่งพระราชบัญญัติการสาธารณสุข พ.ศ. 2535 ตามหลักเกณฑ์ด้านสุขลักษณะในการควบคุมการประกอบกิจการสระว่ายน้ำ หรือกิจการอื่นๆ ในทำนองเดียวกันที่แนบมาพร้อมนี้

ข้อ 3 กรณีที่ราชการส่วนท้องถิ่นใดออกข้อกำหนดของท้องถิ่นว่าด้วยการประกอบกิจการสระว่ายน้ำ หรือกิจการอื่นๆ ในทำนองเดียวกัน ควรจัดให้มีการประชาสัมพันธ์ และประชุมชี้แจงข้อกำหนดของท้องถิ่นดังกล่าวเพื่อให้ผู้ประกอบกิจการได้ทราบโดยทั่วกันด้วย ทั้งนี้เพื่อประโยชน์ในการบังคับใช้ต่อไป

ให้ไว้ ณ วันที่ 20 มกราคม 2550

(นายปราชญ์ บุณยวงศ์วิโรจน์)
ปลัดกระทรวงสาธารณสุข

หลักเกณฑ์ด้านสุขลักษณะ
ในการควบคุมการประกอบกิจการสระว่ายน้ำ หรือกิจการอื่นๆในทำนองเดียวกัน

****

คำแนะนำนี้ให้ใช้กับกิจการสระว่ายน้ำที่เป็นบริการสาธารณะ(Public swimming pool) เช่น กิจการสระว่ายน้ำที่ให้บริการแก่ประชาชนโดยทั่วไป ซึ่งรวมถึงสระว่ายน้ำที่เป็นสวนน้ำ สวนสนุก ที่มีลักษณะเช่นเดียวกับสระว่ายน้ำที่ให้บริการในลักษณะเพื่อการค้า และสระว่ายน้ำที่เปิดให้บริการสาธารณะที่มิใช่การค้าแต่เพื่อสวัสดิการ เช่น สระว่ายน้ำที่ราชการส่วนท้องถิ่นจัดไว้เพื่อสาธารณะประโยชน์ รวมทั้ง สระว่ายน้ำที่เป็นของสโมสรของโรงงานที่บริการเฉพาะพนักงาน หรือหน่วยงานองค์กรที่บริการในกลุ่มเฉพาะ ยกเว้นสระว่ายน้ำส่วนบุคคลหรือที่มิได้ให้บริการแก่สาธารณะ

1. สถานที่ตั้ง

1.1 สถานที่ตั้ง ควรห่างจากแหล่งซึ่งอาจทำให้เกิดการปนเปื้อนน้ำในสระว่ายน้ำ เช่น สถานที่เลี้ยงสัตว์ สถานที่ทิ้งหรือรวบรวมมูลฝอย เป็นต้น

1.2 ควรมีรั้วหรือกำแพงเพื่อสุขอนามัยและความปลอดภัยของผู้ใช้บริการ และเพื่อป้องกันไม่ให้บุคคลภายนอกที่ไม่ได้รับอนุญาตไปใช้สระว่ายน้ำ ในช่วงที่ไม่เปิดให้บริการ รวมทั้งป้องกันสัตว์เข้ามาในบริเวณสระว่ายน้ำ

1.3 สถานที่ตั้งและบริเวณของสระว่ายน้ำ รวมทั้งระบบสาธารณูปโภคต้องอยู่ในที่น้ำท่วมไม่ถึง พื้นดินแข็งแรงไม่ทรุดง่าย อยู่ในบริเวณที่มีไฟฟ้า และน้ำประปาเพียงพอ มีทางเข้าออกสะดวก

2. สระว่ายน้ำและอาคารประกอบ

2.1 โครงสร้างสระว่ายน้ำ ควรสร้างด้วยคอนกรีตเสริมเหล็ก หรือวัสดุที่มีความมั่นคงแข็งแรง น้ำซึมไม่ได้ ผนังเรียบ อยู่ในสภาพดี และทำความสะอาดง่าย

2.2 ต้องมีรางระบายน้ำล้นมีฝาปิดรอบสระว่ายน้ำ มีความกว้าง 30-40 เซนติเมตร ไม่เป็นสนิม แข็งแรง ทำความสะอาดง่าย อยู่ในสภาพดี และไม่มีน้ำล้นออกจากราง

2.3 ต้องมีอุปกรณ์ เครื่องมือสำหรับใช้ทำความสะอาดสระว่ายน้ำ ได้แก่ เครื่องดูดตะกอน แปรงขัดสระชนิดลวดทองเหลืองและพลาสติก รวมทั้งตะแกรงช้อนวัสดุแขวนลอย

2.4 ต้องมีที่ว่างสำหรับใช้เป็นทางเดินรอบสระว่ายน้ำ มีความกว้างไม่น้อยกว่า 1.20 เมตร ไม่ลื่น ไม่มีน้ำขัง ทำความสะอาดง่าย

2.5 กรณีที่สระว่ายน้ำใดมีการใช้ระบบการไหลเวียนน้ำเป็นแบบระบบสกิมเมอร์ ควรต้องมีข้อกำหนดเกี่ยวกับการป้องกันอันตรายจากระบบนี้ด้วย

2.6 ความลึกของน้ำ มีป้ายบอกความลึกหรือเลขบอกระดับความลึกที่สามารถมองเห็นได้ชัดเจน ในกรณีที่สระว่ายน้ำนั้นมีความลึกตั้งแต่ 1.5 เมตรขึ้นไป โดยมีตัวเลขแสดงความลึกเป็นระยะๆ อย่างน้อย 3 ระยะ

2.7 ต้องจัดให้มีแสงสว่างเพียงพอทั่วบริเวณสระว่ายน้ำ เพื่อให้มองเห็นได้ชัดเจน ในกรณีที่มีการเปิดใช้สระในเวลากลางคืน

2.8 อาคารประกอบทำด้วยวัสดุมั่นคงแข็งแรง พื้นเรียบ ไม่ลื่นไม่ดูดซึมน้ำ ทำความสะอาดง่าย พื้นลาดเอียงเล็กน้อยเพื่อการระบายน้ำที่ดี

2.9 พื้น ควรทำด้วยวัสดุแข็งแรง เรียบ ไม่ดูดซึมน้ำ ทำความสะอาดง่าย ไม่ลื่น อยู่ในสภาพดี

2.10 จัดให้มีห้องเปลี่ยนเสื้อผ้า ตู้เก็บสิ่งของ ที่วางหรือเก็บรองเท้า สำหรับผู้ใช้บริการในบริเวณทางเข้าสระว่ายน้ำ และมีจำนวนเพียงพอ

2.11 จัดให้มีอ่างล้างมือ บริเวณล้างตัวก่อนลงสระ และที่ล้างเท้า ทางเข้าบริเวณสระว่ายน้ำ และเติมคลอรีนลงในที่ล้างเท้าเพื่อป้องกันการติดเชื้อ

2.12 มีการรักษาความสะอาดรอบอาคารประกอบและพื้นที่โดยรอบอย่างสม่ำเสมอ

2.13 ดูแลมิให้มีการนำสัตว์ทุกชนิดเข้าไปในบริเวณสระว่ายน้ำ หรืออาคารประกอบ

3. ข้อปฏิบัติสำหรับผู้ประกอบกิจการ

3.1 จัดให้มีผู้ควบคุมดูแล ซึ่งผ่านการฝึกอบรมการดูแลคุณภาพน้ำในสระว่ายน้ำตามหลักสุขาภิบาลสิ่งแวดล้อม เพื่อให้มีความรู้เกี่ยวกับการควบคุมคุณภาพน้ำ และการดูแลรักษาสระว่ายน้ำ

3.2. ต้องมีเจ้าหน้าที่ความปลอดภัยประจำสระ (Life guard) อย่างน้อย 1 คน ต่อผู้ใช้บริการไม่เกิน 100 คน กรณีที่เกิน 100 คน เศษของ 100 คน ให้คิดเป็น 100 คน และต้องเป็นผู้ที่มีความชำนาญในการว่ายน้ำและผ่านการอบรมการช่วยชีวิตคนจมน้ำ สามารถให้การปฐมพยาบาลได้ โดยต้องอยู่ประจำสระว่ายน้ำตลอดเวลาที่เปิดบริการ

3.3 ต้องมีการจัดการและควบคุมคุณภาพน้ำให้อยู่ในเกณฑ์มาตรฐาน ดังนี้

3.3.1 ค่าความเป็นกรด-ด่าง (pH)	7.2 – 8.4
3.3.2 คลอรีนอิสระ (Free chlorine)	0.6– 1.0 ส่วนในล้านส่วน
3.3.3 คลอรีนที่รวมกับสารอื่น (Combined chlorine)	0.5 -1.0 ส่วนในล้านส่วน
3.3.4 ค่าความเป็นด่าง (Alkalinity)	80 – 100 ส่วนในล้านส่วน
3.3.5 ความกระด้าง (Calcium hardness)	250 -600 ส่วนในล้านส่วน
3.3.6 กรดไซยานูริก (Cyanuric acid)	30-60 ส่วนในล้านส่วน
3.3.7 คลอไรด์ (Chloride)	ไม่เกิน 600 ส่วนในล้านส่วน

3.3.8 แอมโมเนีย (Ammonia) ไม่เกิน 20 ส่วนในล้านส่วน

3.3.9 ไนเตรท (Nitrate) ไม่เกิน 50 ส่วนในล้านส่วน

3.3.10 โคลิฟอร์มทั้งหมด (Total Coliform Bacteria) น้อยกว่า 10 ต่อน้ำ 100 มิลลิลิตร โดยวิธีเอ็มพีเอ็น(Most Probable Numbers)ในอัตราส่วน 100 มิลลิลิตร

3.3.11 ตรวจไม่พบฟีคอลโคลิฟอร์ม (Fecal coliform)

3.3.12 ตรวจไม่พบจุลินทรีย์หรือตัวบ่งชี้จุลินทรีย์ที่ทำให้เกิดโรค (ได้แก่*Escherichia coli Staphylococcus aureus Pseudomonas aeruginosa*)

3.4 จัดให้มีการเก็บตัวอย่างเพื่อตรวจวิเคราะห์คุณภาพน้ำ ตามเกณฑ์มาตรฐานดังนี้

3.4.1 การเก็บตัวอย่างต้องทำอย่างน้อย 2 จุด โดยเก็บจากส่วนลึกและส่วนตื้น ขณะที่มีผู้ใช้สระว่ายน้ำมากที่สุด

3.4.2 ตรวจวิเคราะห์ปริมาณคลอรีนอิสระคงเหลือ และค่าความเป็นกรด-ด่าง อย่างน้อยวันละ 2 ครั้ง ก่อนเปิดและหลังปิดบริการ หากมีผู้ใช้บริการเป็นจำนวนมาก หรือเป็นวันที่มีแสงแดดจัดควรตรวจสอบปริมาณคลอรีน และค่าความเป็นกรด-ด่างในระหว่างวันด้วย กรณีใช้คลอรีนชนิดกรดไตรคลอโรไอโซไซยานูริค ต้องตรวจหาค่ากรดไซยานูริคด้วย

3.4.3 ตรวจวิเคราะห์ปริมาณโคลิฟอร์มทั้งหมด (Total Coliform Bacteria) และฟีคอลโคลิฟอร์ม (Fecal coliform) อย่างน้อยเดือนละ 1 ครั้ง

3.4.4 ตรวจวิเคราะห์คุณภาพน้ำทางเคมี และชีวภาพ ตามเกณฑ์มาตรฐานตามที่กำหนดในข้อ 3.3 ครบทุกข้อมูล อย่างน้อยปีละ 1 ครั้ง เพื่อประกอบการพิจารณาขอหรือต่อใบอนุญาต

3.5 จัดหาเครื่องมือสำหรับตรวจวิเคราะห์คุณภาพน้ำไว้ประจำ รวมทั้งบันทึกผลการตรวจวิเคราะห์ และข้อมูลอื่นที่จำเป็น ดังนี้

3.5.1 เครื่องมือที่ใช้ตรวจวิเคราะห์ปริมาณคลอรีน ต้องสามารถตรวจวิเคราะห์ได้ในช่วง 0.2 – 2 ส่วนในล้านส่วน

3.5.2 เครื่องมือที่ใช้ตรวจวิเคราะห์ค่าความเป็นกรด-ด่าง ต้องสามารถตรวจวัดได้อย่างน้อยช่วง 3-9 และสามารถอ่านค่าได้ช่วงละ 1

3.5.3 มีการบันทึกข้อมูลจำนวนผู้ใช้สระว่ายน้ำในแต่ละวัน แยกเพศและอายุ ระยะเวลาที่ใช้สระว่ายน้ำ

3.6 ต้องจัดให้มีป้ายแสดงข้อปฏิบัติสำหรับผู้ใช้บริการติดไว้ในบริเวณสระว่ายน้ำ ให้มองเห็นชัดเจน และควรมีข้อความอย่างน้อยดังนี้

3.6.1 ต้องสวมชุดว่ายน้ำที่สะอาด

3.6.2 ต้องชำระล้างร่างกายก่อนลงสระทุกครั้ง

3.6.3 ผู้ที่เป็นโรคตาแดง โรคผิวหนัง เป็นหวัด หูน้ำหนวก หรือโรคติดต่ออื่นๆ ห้ามลงเล่นในสระว่ายน้ำ

3.6.4 ห้ามนำสัตว์เลี้ยงเข้ามาในบริเวณสระว่ายน้ำ

3.6.5 ห้ามปัสสาวะ บ้วนน้ำลาย หรือสั่งน้ำมูกลงในน้ำ

3.6.6 ห้ามทำสระว่ายน้ำสกปรก

3.6.7 จำนวนผู้ใช้บริการมากที่สุด ที่สระว่ายน้ำสามารถรองรับได้

3.6.8 วิธีการปฐมพยาบาลช่วยคนจมน้ำ

3.7 ต้องดูแลบำรุงรักษาเครื่องกรองน้ำตามระยะเวลาที่สมควรเพื่อให้ทำงานได้เต็มประสิทธิภาพ

4. การจัดการเกี่ยวกับสารเคมี

4.1 สถานที่เก็บสารเคมี ต้องมีป้ายระบุว่า "สถานที่เก็บสารเคมีอันตราย" และ "ห้ามเข้า" มีการระบายอากาศดี และมีการป้องกันน้ำซึมเข้าภาชนะบรรจุสารเคมี และมีการจัดเก็บสารเคมีเป็นไปตามกฎหมายที่เกี่ยวข้อง

4.2 สารเคมีที่ใช้ต้องมีฉลากระบุชื่อสารเคมี ส่วนผสม หรือส่วนประกอบที่เป็นอันตราย วิธีการใช้และวิธีการปฐมพยาบาลในกรณีฉุกเฉิน หรือตามที่กฎหมายอื่นกำหนด

4.3 ในการใช้สารเคมีต้องปฏิบัติตามที่ระบุไว้ในฉลาก และไม่นำสารเคมีหมดอายุมาใช้ ในกรณีที่ไม่มีระบบการเติมสารเคมีแบบอัตโนมัติให้เติมสารเคมีลงในสระว่ายน้ำในขณะที่ปิดบริการแล้ว

4.4 สถานที่ทำงานที่เกี่ยวข้องกับการใช้สารเคมี ต้องมีแสงสว่างเพียงพอ เพื่อป้องกันการเกิดอุบัติเหตุอันเนื่องจากพนักงานไม่สามารถมองเห็นสิ่งต่าง ๆ ได้อย่างชัดเจน ค่ามาตรฐานแสงสว่างในบริเวณต่างๆ ควรเป็นดังนี้

- ห้องสูบจ่ายสารเคมีไม่น้อยกว่า 100 ลักซ์
- ห้องเครื่องกรองน้ำ ไม่น้อยกว่า 50 ลักซ์
- ห้องหรือสถานที่เก็บสารเคมีไม่น้อยกว่า 50 ลักซ์

4.5 ต้องมีมาตรการในการป้องกันการสัมผัสสารเคมีของคนงาน เช่น กำหนดขั้นตอนการทำงานที่ปลอดภัย จัดหาอุปกรณ์ป้องกันอันตรายส่วนบุคคลที่เหมาะสมให้คนงาน รวมทั้งประเมินการสัมผัสสารเคมีอันตรายของคนงานที่ทำหน้าที่เติมสารเคมี และมีผลไว้ให้เจ้าหน้าที่ตรวจสอบอย่างน้อยปีละหนึ่งครั้ง

4.6 ในขณะทำงานกับสารเคมี ให้ผู้ปฏิบัติงานสวมอุปกรณ์ป้องกันอันตรายส่วนบุคคลที่เหมาะสม เช่น สวมหน้ากาก และสวมถุงมือในขณะปฏิบัติเกี่ยวกับสารเคมี เป็นต้น

4.7 ห้ามสูบบุหรี่ ดื่มน้ำหรือรับประทานอาหารในห้องจัดเก็บสารเคมี

4.8 ดูแลความสะอาดอย่างสม่ำเสมอ หากสารเคมีหกรั่วไหล ต้องทำความสะอาดทันที

5. การจัดการสิ่งปฏิกูล น้ำเสีย และมูลฝอย

5.1. จัดให้มีห้องน้ำ ห้องส้วม และการบำบัดสิ่งปฏิกูลดังนี้

5.1.1 มีห้องน้ำ ห้องส้วมแยกจากกัน โดยมีแบบและจำนวนตามที่กำหนดในกฎหมายว่าด้วยการควบคุมอาคารและกฎหมายอื่นที่เกี่ยวข้อง

5.1.2 ลักษณะของห้องส้วม การบำบัด และการกำจัดสิ่งปฏิกูลต้องถูกต้องตามหลักสุขาภิบาล

5.1.3 ต้องดูแลรักษาความสะอาดของห้องน้ำและห้องส้วมเป็นประจำทุกวันที่เปิดให้บริการ

5.1.4 ภายในห้องน้ำควรมีวัสดุอุปกรณ์ตามความจำเป็นและเหมาะสม

5.2 มีการบำบัดน้ำเสียให้มีคุณภาพได้มาตรฐานก่อนระบายสู่ท่อระบายน้ำสาธารณะ ซึ่งส่วนประกอบของระบบการจัดการน้ำเสีย ประกอบด้วย

5.2.1 ตะแกรงดักมูลฝอย สำหรับดักเศษมูลฝอยจากน้ำเสีย

5.2.2 ระบบรวบรวมน้ำเสีย น้ำจากส่วนต่างๆของอาคารไหลมารวมกันที่ถังรวบรวมน้ำเพื่อรอการบำบัด น้ำที่ล้นออกจากบ่อรวบรวมนี้จะไหลเข้าสู่บ่อบำบัด

5.2.4 ระบบบำบัดน้ำเสียต้องมีวิธีการบำบัดน้ำเสียที่เหมาะสม ไม่ก่อให้เกิดเหตุเดือดร้อนรำคาญและเป็นอันตรายต่อสุขภาพของชุมชน

5.2.5 รางระบายน้ำทิ้ง รางหรือท่อสำหรับระบายน้ำทิ้ง ควรมีตะแกรงวางปิดรางเพื่อกรองเศษผงต่างๆ และป้องกันหนู นอกจากนี้ทางเปิดของท่อระบายน้ำออกสู่ท่อสาธารณะควรมีตะแกรงปิดเพื่อป้องกันหนูด้วย

5.3 จัดให้มีการจัดการมูลฝอยดังนี้

5.3.1 ควรมีการคัดแยกมูลฝอยและมีภาชนะรองรับมูลฝอยแยกตามประเภท

5.3.2 มีภาชนะรองรับมูลฝอยที่เพียงพอตามหลักสุขาภิบาล

5.3.3 ล้างทำความสะอาดภาชนะรองรับมูลฝอยและบริเวณที่วางภาชนะอยู่เสมอ

5.3.4 รวบรวมมูลฝอยจากภาชนะรองรับมูลฝอยไปยังที่พักมูลฝอยรวม หรือนำไปกำจัดทุกวัน โดยเฉพาะมูลฝอยที่เน่าเสียได้ง่าย

5.3.5 กำจัดมูลฝอยด้วยวิธีที่ถูกต้องตามหลักสุขาภิบาล และเป็นไปตามข้อกำหนดท้องถิ่น

5.3.6 ดูแลมิให้เกิดการทิ้งมูลฝอยเกลื่อนกลาดภายในสถานประกอบกิจการและบริเวณโดยรอบ

6. การสุขาภิบาลอาหารและน้ำดื่ม

6.1 ในกรณีมีการจำหน่ายอาหาร ต้องปฏิบัติตามหลักสุขาภิบาลอาหาร และตามข้อกำหนดของท้องถิ่น

6.2 ต้องมีน้ำดื่มที่ได้คุณภาพตามมาตรฐานน้ำดื่มไว้บริการอย่างเพียงพอ

6.3 ลักษณะการนำน้ำมาดื่ม ต้องไม่ก่อให้เกิดความสกปรกหรือการปนเปื้อน เช่น ใช้ระบบน้ำกด ใช้แก้วส่วนตัว ใช้แก้วกระดาษที่ใช้ครั้งเดียวแล้วทิ้ง และใช้แก้วส่วนกลางที่ใช้ดื่มเพียงครั้งเดียว แล้วนำไปล้างทำความสะอาดก่อนนำมาใช้ใหม่ เป็นต้น ทั้งนี้ให้จัดทำป้ายหรือมีข้อความการปฏิบัติไว้ด้วย

7. การป้องกันควบคุมสัตว์และแมลงนำโรค

7.1 ภายในสถานประกอบกิจการไม่ควรมีหนู แมลงวัน และแมลงสาบ

7.2 ต้องมีการป้องกัน ควบคุม กำจัดสัตว์และแมลงนำโรคโดยเฉพาะหนู แมลงวัน และแมลงสาบอย่างถูกต้องตามหลักสุขาภิบาล

8. การดูแลสุขภาพและความปลอดภัย

8.1 ต้องกำหนดให้มีผู้ดูแลมาด้วย กรณีที่นำเด็กอายุต่ำกว่า 10 ปี ที่ยังว่ายน้ำไม่เป็นและผู้สูงอายุที่ไม่สามารถดูแลตัวเองได้มาใช้บริการสระว่ายน้ำ

8.2 จัดให้มีอุปกรณ์ช่วยชีวิต ดังนี้

8.2.1 โฟมช่วยชีวิต อย่างน้อย 2 อัน

8.2.2 ห่วงชูชีพ ขนาดเส้นผ่าศูนย์กลางภายใน 15 นิ้ว หรือทุ่นลอย ผูกไว้กับเชือกยาวไม่น้อยกว่าความกว้างของสระว่ายน้ำ อย่างน้อย 2 อัน

8.2.3 ไม้ช่วยชีวิต หรือวัตถุอื่นใด มีความยาวไม่น้อยกว่า 3.5 เมตร น้ำหนักเบา อย่างน้อย 1 อัน และต้องวางไว้ที่ปลายลู่ส่วนลึกของสระว่ายน้ำ

8.2.4 เครื่องช่วยหายใจ สำหรับผู้ใหญ่ และสำหรับเด็ก อย่างละ 1 ชุด

8.2.5 ห้องปฐมพยาบาลพร้อมชุดปฐมพยาบาลที่พร้อมใช้งานได้ตลอดเวลาไว้ประจำสระว่ายน้ำและอยู่ในบริเวณที่ใกล้ที่สุด

8.3 มีอุปกรณ์สื่อสารที่สามารถติดต่อบุคคลหรือสถานที่สำคัญๆ เช่น โรงพยาบาล และสถานีตำรวจ เพื่อขอความช่วยเหลือเมื่อเกิดเหตุฉุกเฉินต่างๆ เช่น เพลิงไหม้ หรือมีคนจมน้ำ และต้องปิดประกาศหมายเลขโทรศัพท์ของสถานที่ดังกล่าวไว้ในที่เห็นได้ชัดเจนและเป็นข้อมูลปัจจุบันอยู่เสมอ

9. เหตุรำคาญ

มีการควบคุมมิให้เกิดเหตุรำคาญ ซึ่งมาจากกิจกรรมการดำเนินการต่างๆ

****