


ภาคผนวก ข
เอกสารประกอบการปฏิบัติตามมาตรการด้านสิ่งแวดล้อม

- ข1 เอกสารแบบแปลนพื้นที่สีเขียว
 - ข2 เอกสารแบบแปลนอาคารในโครงการ
 - ข3 เอกสารแบบแปลนระบบบำบัดน้ำเสียของโครงการ
 - ข4 เอกสารการสูบน้ำก่อนส่วนเกินจากระบบระบายน้ำในโครงการ
 - ข5 เอกสารแผนอพยพหนีไฟ
 - ข6 เอกสารตรวจเช็คอุปกรณ์ป้องกันอัคคีภัย
-


ภาคผนวก ข1
เอกสารแบบแปลนพื้นที่สีเขียว



รูปที่ 2.1-1 ผังบริเวณ (Lay Out) ของโครงการ

ภาคผนวก ข2


เอกสารแบบแปลนอาคารในโครงการ



LAY OUT PLAN
SCALE 1:200

ภาคผนวก ข3


เอกสารแบบแปลนระบบบำบัดน้ำเสียของโครงการ




FLOW DIAGRAM OF WASTE WATER TREATMENT

LIST OF EQUIPMENT FOR WASTEWATER TREATMENT SYSTEM

ITEM	SYMBOL	DESCRIPTION	LOCATION	SYSTEM COMPONENT AND SPECIFICATION	EACH CAPACITY	ELECTRICAL MOTOR DATA			POWER CONTROL CENTER	CONTROL FUNCTION AND CONTROL DEVICES	REMARKS
						APPROX. HP.	SPEED RPM	V/F HZ			
1	EXP-1 EXP-2	EQUALIZING PUMP	EQUALIZING TANK	SUBMERSIBLE SEWAGE PUMP/NON CLOG TYPE WITH GUIDE RAIL, LIFTING CHAIN, AND INSULATION CLASS F	Q=5 CUM./HR. H=7 M.	0.4	≤ 3,000	380/3/50	SMCC-02	BOTH MANUAL AND AUTOMATIC OPERATED WITH FLOW SWITCHES - LOW LEVEL STOP - INTERMEDIATE LEVEL START - HIGH LEVEL ALARM - IF ONE PUMP CAN NOT HANDLE THE INFLOW, THE OTHER CAN START THE SECOND PUMP AUTOMATICALLY	
2	EJA-1	AIR EJECTOR	EXCESS SLUDGE STORAGE TANK	SUBMERSIBLE EJECTOR WITH SILENCER/VALVE SET, GUIDE RAIL, LIFTING CHAIN, AND INSULATION CLASS F	AIR EMISSION 3 VOLUME=11 M ³ /hr AT 3.00M. WATER DEPTH	0.75	≤ 3,000	380/3/50	SMCC-02	BOTH MANUAL AND AUTOMATIC OPERATED BY 24 HRS. TIMER	
3	SA-1 SA-2 SA-3 SA-4	SUBMERSIBLE AERATOR	AERATION TANK	SUBMERSIBLE AERATOR WITH SILENCER/VALVE SET, GUIDE RAIL, LIFTING CHAIN, AND INSULATION CLASS F	AIR EMISSION 3 VOLUME=22 M ³ /hr AT 3.00M. WATER DEPTH	1.5	≤ 3,000	380/3/50	SMCC-02	SA-1 AS ITEM 2	
4	SLP-1 SLP-2	RETURN SLUDGE PUMP	SLUDGE HOLDING TANK	SA-1 AS ITEM 1	Q=3 CUM./HR. H=7 M.	0.4	≤ 3,000	380/3/50	SMCC-02	SA-1 AS ITEM 1	
5	EFP-1 EFP-2	EFFLUENT PUMP	EFFLUENT TANK	SA-1 AS ITEM 1	Q=10 CUM./HR. H=8 M.	0.75	≤ 3,000	380/3/50	SMCC-02	SA-1 AS ITEM 1	




แปลนพื้นที่ 1




แปลนพื้นที่ 2


日期	星期	地点	内容	备注
1952.10.1	星期一	教室	数学	
1952.10.2	星期二	教室	语文	
1952.10.3	星期三	教室	数学	
1952.10.4	星期四	教室	语文	
1952.10.5	星期五	教室	数学	
1952.10.6	星期六	教室	语文	
1952.10.7	星期日	教室	数学	




หมายเลขเอกสาร PS-8 (ก. 2)




หมายเลข PS-7, PS-1A (หน้า 2)



หมายเลขห้องทดสอบ PS-6, PS-2A (หลัง)




ANALYTICAL PS-5 (4.2)



_____ 96302, 17424


_____ 96304, 17424




1000 5000




7




SECTION 5 150




SECTION 1:50




SECTION ② 1:50



SECTION ④ 1:50




DETAIL OF OUTLET GUTTER AT SEDIMENTATION TANK




2020000


ELECTRODE WIRED TO SMCC-01
MANHOLE W/CLEAR OPENING Ø 300 Ø 20




SECTION A
ROOF TANK DETAIL
NOT TO SCALE



SECTION C
UNDERGROUND WATER TANK AT SUMP PIT
NOT TO SCALE



SECTION
SCALE 1:20



PLAN
SCALE 1:20

DETAIL OF MANHOLE COVER
SCALE 1:20

COLD WATER SUPPLY PUMPS (CWP) CONTROLLER

A) ROOF WATER STORAGE TANK LIQUID LEVEL CONTROL (FLOATLESS SWITCH)

- 1) THE AUTOMATIC OPERATION OF THE PUMPS SHALL BE CONTROLLED BY THE LIQUID LEVEL CONTROL WHEN THE ON-OFF-AUTO SELECTOR SWITCH IS SET ON AUTO AND STARTER TO "ON" POSITION
- 2) THE SEQUENCE OF OPERATION SHALL BE AS FOLLOWS -
 - 2.1) NORMAL OPERATION IS WHEN WATER LEVEL FLUCTUATES BETWEEN ELECTRODE "B" & "C"
 - 2.2) WHEN WATER LEVEL RISES UP TO ELECTRODE "B" BOTH PUMPS WILL CUT-OFF
 - 2.3) ELECTRODE "A" WHICH SHOULD BE SET 100 mm ABOVE ELECTRODE "B" IS FOR ACTUATING HIGH WATER ALARM
 - 2.4) IF WATER LEVEL DROP TO ELECTRODE "C" LEVEL, THE LEAD PUMP WILL BE ON
 - 2.5) IF WATER LEVEL CONTINUE DROPPING TO ELECTRODE "D" LEVEL, THE LAG PUMP WILL BE ON
 - 2.6) ELECTRODE "D" IS FOR ACTUATING LOW LEVEL ALARM AND BOOSTER PUMP CUT-OFF
- 3) THE CONTROL RELAY SHALL BE INTERLOCKED WITH MOTOR STARTER CIRCUIT TO PROVIDE THE ABOVE SEQUENCE OF OPERATION
- 4) THE AUTOMATIC ALTERNATOR STARTER COORDINATION CONTROLLER WITH MANUAL SWITCH IS PROVIDED TO SWITCH THE LEAD PUMP OPERATION EVERY START THE MANUAL SWITCH SHALL ALLOW FOR EITHER PUMP TO BE SELECTED AS BASE PUMP OR FOR AUTOMATIC ALTERNATION

ROOF WATER STORAGE TANK SENSING ELECTRODE SETTING		
SENSING ELECTRODE "A"	M ABOVE TANK BOTTOM	HIGH WATER ALARM
SENSING ELECTRODE "B"	M ABOVE TANK BOTTOM	ALL PUMPS STOP
SENSING ELECTRODE "C"	M ABOVE TANK BOTTOM	LEAD PUMP ON
SENSING ELECTRODE "D"	M ABOVE TANK BOTTOM	LAG PUMP ON
SENSING ELECTRODE "E"	M ABOVE TANK BOTTOM	LOW LEVEL ALARM AND BOOSTER PUMP CUT-OFF

B) UNDERGROUND COLD WATER STORAGE TANK LIQUID CONTROL (FLOATLESS SWITCH)

- 1) THREE SENSING POINTS OF ELECTRODES WILL BE SET FOR U/G WATER TANK
- 2) CONTROL FUNCTIONS OF EACH ELECTRODE WILL BE AS FOLLOWS

U/G COLD WATER STORAGE TANK SENSING ELECTRODE SETTING	
SENSING ELECTRODE "1"	HIGH WATER LEVEL ALARM
SENSING ELECTRODE "2"	PUMPS CUT-IN AUTOMATICALLY
SENSING ELECTRODE "3"	PUMPS CUT-OFF & LOW LEVEL ALARM

EQUIPMENT SCHEDULE FOR SEWAGE TREATMENT PLANT

ITEM	TYPE OF EQUIPMENT	SYMBOL	QTY.	LOCATION	APPLICATION	DESCRIPTION	POWER CONTROL CENTER	CONTROL FUNCTION AND CONTROL DEVICES
1	TREATED SEWAGE LIFTING PUMPS (EFFLUENT PUMPS)	EFP-1 & EFP-2	2 SETS	PUMP BUMP OF TREATMENT PLANT	TRANSFER TREATED WASTE TO SITE DRAIN	SUBMERSIBLE PUMPS FOR SEWAGE HANDLING NON-CLOG TYPE AND INSULATION CLASS F CAPACITY 20 cu.m./hr AT 0.0 m TDH MOTOR 1.5 kw (2 HP) Approx. ACCESSORIES - LIFTING CHAIN - CHECK VALVE GATE VALVE - GUIDE RAIL	SMCC-02	BOTH MANUAL AND AUTOMATIC OPERATED WITH FLOAT SWITCHES SEE ALSO LEVEL CONTROL & SEQUENCE OF PUMP OPERATION
2	SUBMERSIBLE AERATOR	SA-1 & SA-2	2 SETS	FIXED FILM TANK	SUPPLY AIR TO FIXED FILM AERATION TANK	SUBMERSIBLE AERATOR W/LIFTING CHAIN AND INSULATION CLASS F ACCESSORIES: SUCTION SILENCER VALVE SET CAPACITY 11 Nm ³ /hr AT 3.0m AQUA-DEPTH MOTOR RATING 1 HP Approx	SMCC-02	BOTH MANUAL AND AUTOMATIC OPERATED BY 24 HRS TIMER
3	FLOAT SWITCH (LEVEL REGULATOR)		1 SETS	PUMP BUMP OF TREATMENT PLANT	TO CONTROL PUMP ON-OFF & ALARM	FOUR CONTROL LEVELS ARE REQUIRED EACH SET		
4	PLASTIC MEDIA FOR ANAEROBIC FILTER			ANAEROBIC FILTER TANK OF TREATMENT PLANT		SEE NOTE 4 BELOW		
5	PLASTIC MEDIA FOR FIXED FILM AERATION			FIXED FILM TANK OF TREATMENT PLANT		SEE NOTE 5 BELOW		

SEWAGE TREATMENT PLANT			
LEVEL CONTROL & SEQUENCE OF PUMP OPERATION (AUTOMATIC MODE)			
LEVEL	(FROM BOTTOM OF TANK)	CYCLE 1.	CYCLE 2.
4 HWL	1.80 m	ALARM	ALARM
3	1.60 m	P2 START	P1 START
2	1.20 m	P1 START	P2 START
1 LWL	0.30 m	ALL STOP	ALL STOP
1 CONTROL LEVEL MAY BE ADJUSTED TO SUIT EXISTING CONDITION 2 ALARM CONTROL FOR AUTOMATIC MODE 2.1 VISIBLE & AUDIBLE ALARM WHEN WATER REACH LEVEL 4 2.2 WHEN PUMP WAS IN UNNORMAL CONDITION OVERLOAD OPERATE AT NO FLOW NOT OPERATE OR STOP AT LEVEL 2,3,4 NOTES: 1 PUMPS SHALL BE SUBMERSIBLE TYPE COMPLETE WITH DUCK FOOT BEND LIFTING CHAIN FOR EACH SET PUMP CAPACITY SHALL BE AS SHOWN ON SCHEDULE. CONTROL SHALL BE PROVIDED FOR BOTH AUTOMATIC & MANUAL OPERATION 2 PIPE FOR TREATMENT PLANT CONNECTION PIPES BETWEEN EACH COMPARTMENT SHALL BE PVC 1.5 TO 17.2523 PIPES FROM BLDG TO PLANT SHALL CONFORM TO PLUMBING WORK SPECIFICATION 3 FLOAT SWITCH OR LIQUID LEVEL CONTROL SHALL BE MERCURY SWITCH TYPE IN POLYPROPYLENE CASING. CABLE CORD SHALL BE MADE OF PVC FLOAT SWITCH SHALL BE FREELY SUSPENDED AT THE DESIGNED DEPTH BY ITS OWN CABLE TO ACTUATE THE SIGNAL FOR ALL PUMPS AT CERTAIN LEVELS 4 PLASTIC MEDIA FOR ANAEROBIC FILTER TANK SHALL BE MADE OF RIGID POLY VINYL CHLORIDE (PVC) CROSS FLOW CONFIGURATION. SPECIFIC SURFACE AREA 110 sq m /cu.m. OF MEDIA 87% VOID RATIO 5 PLASTIC MEDIA FOR FIXED FILM TANK SHALL BE MADE OF RIGID POLY VINYL CHLORIDE (PCV) CROSS FLOW CONFIGURATION. SPECIFIC SURFACE AREA 240 sq m /cu.m. OF MEDIA			



ภาคผนวก ข4

เอกสารการสุบตะกอนส่วนเกินจากระบบระบายน้ำในโครงการ

ใบเสนอราคา

วันที่ 20/1/66

นิติบุคคลอาคารชุด ลาซาลพาร์ค อาคารบี
5 ซอยลาซาล10 ถนนสุขุมวิท 105 แขวงบางนา เขตบางนา กรุงเทพฯ 10260
โทร. 096-847-8615
id. 0994000208341

ดูดส้วม ตักกาก ไล่อื้อ เดิมจุลลินทรีย์

จำนวนเงิน 20000
(สองหมื่นบาทถ้วน)

หมายเหตุ พนักงานมีใบเซอร์ผ่านการอบรมที่อันอากาศ อุปกรณ์เซฟตี้ครบ
หากมีข้อสงสัย กรุณาติดต่อ
นายศตวรรษ สัมเชื้อ
0829408461

สัญญาจ้าง และกำจัดสิ่งปฏิกูล เลขที่ 4884

ใบเสร็จรับเงิน

วันที่ 8 เดือน 2 พ.ศ. 25 67

ได้รับเงินจาก นิติบุคคลอาคารชุด ลาซาลพาร์ค

ชำระค่าสัญญาจ้าง จำนวน ลิตร ลิตรละ บาท

เป็นเงินจำนวน 20,000 บาท จำนวนรถ รถ รถละ บาท

สองหมื่นบาทถ้วน




บาท

ได้รับเงินค่าสัญญาจ้าง และสิ่งปฏิกูลไว้ถูกต้องเรียบร้อยแล้ว



ลงชื่อ ผู้รับเงิน



ภาพก่อนการสูบล้างบ่อเกรอะ 08/02/67



ภาพหลังการสูบล้างบ่อเกรอะ 08/02/67




ภาคผนวก ข5
เอกสารแผนอพยพหนีไฟ


แผนอพยพหนีไฟ

และแผนการป้องกันระงับอัคคีภัย


แผนอพยพหนีไฟ




ขั้นตอนการปฏิบัติตามแผนและระดับอัคคีภัยขั้นต้น (สามารถระบุได้)



ขั้นตอนการปฏิบัติตามแผนระดับอัคคีภัยหลัก (ขั้นร้ายแรง)





ขั้นตอนการปฏิบัติตามการฉุกเฉิน (แผนปฏิบัติการยามวิกาล / วันหยุดราชการ)



แผนการซ่อมอพยพหนีไฟ ของผู้ใช้อาคาร

ตัวอย่างที่ 1
การทำแผนการดับเพลิง
ตามคู่มือการฝึกอบรมการดับเพลิงขั้นต้น กรมสวัสดิการและคุ้มครองแรงงาน





ภาพ ตัวอย่างแผนอพยพหนีไฟ


ที่มา : คู่มือการฝึกอบรมการดับเพลิงขั้นต้น กรมสวัสดิการและคุ้มครองแรงงาน

ตารางหน้าที่ของผู้ปฏิบัติงานตามโครงสร้าง

ผู้ปฏิบัติงาน	หน้าที่รับผิดชอบ
ผู้อำนวยการ ดับเพลิง	ให้ปฏิบัติ ดังนี้ 1. รับฟังรายงานต่างๆ เพื่อสั่งการการใช้แผนต่างๆ 2. ขอความช่วยเหลือจากหน่วยงานที่เกี่ยวข้อง 3. รายงานผลการเกิดเพลิงไหม้ต่อผู้บังคับบัญชาาระดั่งสูงขึ้นไป 4. ให้ข่าวแก่สื่อมวลชน
ฝ่ายไฟฟ้า	ให้ปฏิบัติ ดังนี้ 1. เมื่อเกิดเพลิงไหม้ให้รับเข้าที่เกิดเหตุ เพื่อรับคำสั่งตัดไฟจากฝ่ายปฏิบัติการ 2. รับคำสั่งจากผู้อำนวยการดับเพลิง
ฝ่ายปฏิบัติการ	ให้ปฏิบัติ ดังนี้ 1. เมื่อเกิดเพลิงไหม้ในพื้นที่ให้หัวหน้าฝ่ายปฏิบัติการแยกชุดปฏิบัติการออกเป็น 2 ชุด คือ ชุดควบคุมเครื่องจักรและชุดดับเพลิง 1.1 ชุดควบคุมเครื่องจักร เมื่อเกิดเพลิงไหม้ในพื้นที่ใด ให้ชุดควบคุมเครื่องจักรทำการควบคุมเครื่องจักรให้ทำงานต่อไปจนกว่าจะได้รับคำสั่งให้หยุดเครื่องจากหัวหน้าฝ่ายปฏิบัติการ กรณีที่ไม่สามารถเดินเครื่อง หรือได้รับคำสั่งให้หยุดเครื่อง ให้ชุดควบคุมเครื่องจักรไปช่วยทำการดับเพลิง 1.2 ชุดดับเพลิง เมื่อเกิดเพลิงไหม้ในพื้นที่ตัวเองไม่ว่ามากหรือน้อย ชุดปฏิบัติการชุดนี้จะแยกตัวออกจากการควบคุมเครื่องจักรออกทำการดับเพลิงโดยทันทีที่เกิดเพลิงไหม้โดยไม่ต้องหยุดเครื่องและให้ปฏิบัติการภายใต้คำสั่งของหัวหน้าฝ่ายปฏิบัติในพื้นที่ ในการปฏิบัติการหากจำเป็นต้องขอความช่วยเหลือจากหน่วยอื่นให้หัวหน้าฝ่ายปฏิบัติการสั่งดำเนินการ 2. ทันทีที่ทราบเหตุเพลิงไหม้ในพื้นที่ของตัวเอง ให้แจ้งข่าวโทรศัพท์ถึงเจ้าหน้าที่ความปลอดภัยถึงผู้อำนวยการดับเพลิง และโทรศัพท์แจ้งศูนย์รวมข่าว
ฝ่ายสื่อสารและ ประสานงาน	ให้ปฏิบัติ ดังนี้ 1. คอยช่วยเหลือประสานงานระหว่างบุคคลที่เกี่ยวข้อง 2. รับคำสั่งจากผู้อำนวยการดับเพลิง และติดต่อผ่านศูนย์รวมข่าว 3. สั่งการแทนผู้อำนวยการดับเพลิง ถ้าได้รับมอบหมาย


ผู้ปฏิบัติงาน	หน้าที่รับผิดชอบ
หน่วยจัดหาและสนับสนุนในการดับเพลิง	ให้เจ้าหน้าที่ความปลอดภัยคอยช่วยเหลือ ดังนี้
ผู้ประสานงาน	1. ช่วยเหลือประสานงาน ผู้อำนวยการดับเพลิง ยามรักษาการณ์และผู้เกี่ยวข้อง 2. คอยรับ – ส่ง คำสั่งจากผู้อำนวยการดับเพลิงในการติดต่อศูนย์ข่าว 3. สั่งการแทนผู้อำนวยการดับเพลิง ในกรณีที่ผู้อำนวยการดับเพลิงมอบหมาย
ยามรักษาการณ์	1. ให้รีบไปยังจุดเกิดเหตุ คอยรับคำสั่งจากผู้อำนวยการดับเพลิงและหัวหน้าฝ่ายประสานงาน 2. ป้องกันมิให้บุคคลภายนอกที่ไม่มีหน้าที่เกี่ยวข้องเข้าก่อนได้รับอนุญาต 3. ควบคุมป้องกันทรัพย์สินที่ฝ่ายเคลื่อนย้ายนำมาเก็บ
ฝ่ายเคลื่อนย้ายภายในภายนอก	1. ให้รับผิดชอบในการกำหนดจุดปลอดภัยอัคคีภัยในการเก็บวัสดุครุภัณฑ์ 2. อำนวยความสะดวกในการเคลื่อนย้ายขนส่งวัสดุครุภัณฑ์ 3. จัดยานพาหนะและอุปกรณ์ขนย้าย
ฝ่ายส่งเสริมปฏิบัติการ	หน้าที่รับผิดชอบ
หน่วยติดต่อดับเพลิงจากพื้นที่อื่น	ให้ปฏิบัติดังนี้ 1. ให้แจ้งสัญญาณ Safety Order System (SOS) 2. พนักงานที่ทราบเหตุเพลิงไหม้และต้องการเข้ามาช่วยเหลือดับเพลิงให้รายงานตัวต่อผู้อำนวยการดับเพลิงเพื่อทำการแบ่งเป็นชุดช่วยเหลือส่งเสริมการปฏิบัติงาน 3. สำหรับการเกิดอัคคีภัยในบริเวณเครื่องจักร ชุดดับเพลิงควรมาจากชุดดับเพลิงในสถานที่นั้นผู้ที่มาช่วยเหลือควรช่วยเหลือในการลำเลียงอุปกรณ์ดับเพลิง
หน่วยเดินเครื่องสูบน้ำฉุกเฉิน	ให้ปฏิบัติดังนี้ 1. ให้เดินเครื่องสูบน้ำดับเพลิงทันทีที่ได้รับแจ้งเหตุเพลิงไหม้ 2. ทำการควบคุมดูแลเครื่องสูบน้ำดับเพลิงขณะที่เกิดเพลิงไหม้ 3. ในเวลาปฏิบัติให้ตรวจสอบเครื่องมือ อุปกรณ์ใช้งานตามรายการตรวจเช็ค
ศูนย์รวมข่าว / สื่อสาร	ให้ปฏิบัติ ดังนี้ 1. เมื่อทราบข่าวเกิดเพลิงไหม้จะต้องทำการตรวจสอบข่าว 2. แจ้งเหตุเพลิงไหม้ 3. ติดตามข่าว แจ้งข่าวเป็นระยะ 4. ติดต่อขอความช่วยเหลือ (ถ้ามีการสื่อสาร) 5. แจ้งข่าวอีกครั้งเมื่อเพลิงสงบ

ตัวอย่างที่ 2
การเขียนแผนฉุกเฉินและการกำหนดหน้าที่ปฏิบัติ



แผนระบบอัตรากำลัง

ลำดับขั้นตอนการปฏิบัติงานเมื่อพนักงานพบเหตุเพลิงไหม้



ภาพ แผนการดับเพลิงและวิธีการดับเพลิงและตัวอย่างลำดับขั้นตอนการปฏิบัติงานเมื่อพนักงานพบเหตุเพลิงไหม้

ที่มา : คู่มือการฝึกอบรมการดับเพลิงขั้นต้น, กรมสวัสดิการและคุ้มครองแรงงาน

ภาคผนวก ข6

เอกสารตรวจเช็คอุปกรณ์ป้องกันอัคคีภัย

ใบตรวจสอบอันดับเพลิง
จุดติดตั้ง วิทยาลัยพาร์ค อคารบิ ชั้น 1 ปีที่ติดตั้ง 2566

ว/ค/ป ตรวจ	ตรวจสอบอุปกรณ์					ผู้ตรวจสอบ
	สลัก สายฉีด	คันบีบ ข้อต่อ	สภาพถัง	เกจวัด	สารเคมี	
21/3/67	✓	✓	✓	✓	✓	
20/4/67	✓	✓	✓	✓	✓	
20/5/67	✓	✓	✓	✓	✓	
20/6/67	✓	✓	✓	✓	✓	
21/7/67	✓	✓	✓	✓	✓	
20/8/67	✓	✓	✓	✓	✓	
20/9/67	✓	✓	✓	✓	✓	
20/10/67	✓	✓	✓	✓	✓	
21/11/67	✓	✓	✓	✓	✓	
20/12/67	✓	✓	✓	✓	✓	