

เอกสารสอบเทียบเครื่องมือที่ใช้ในการวิเคราะห์

BSC Certification Test Report

Page 1 of 6

Certificate No. : M1439/24

Customer Name : LABORATORY WATER ANALYSIS CENTER COMPANY LIMITED

Customer Address : 1/94 Moo 5 Khan Ham Subdistrict,
Uthai District, Phra Nakhon Si Ayutthaya 13210

Equipment : Biological Safety Cabinet **Class** II **Type** A2

Manufacturer : Microtech

Model : V6-T

Serial No. : 0972k097272

ID No. : WWL 0084

Were in accordance with ☒ EN 12469 ☐ NSF 49 ☐ Manufacturer's specification

Test Date : 15/10/2024

Due Date : 15/10/2025 *or after HEPA filters are replaced or unit is moved*

Test by : Mr. Pawut Wongnarokornkul

Approved by :

(Mr.Krudsada Thinhutaoei)

Authorized Signatory

Issued Date : 16/10/2024

This calibration certificate documents the traceability to national standards, which realize the unit of measurement according to the International System of Units (SI).

This certificate may not be reproduced other than in full except with the prior written approval of the Megafil Company Limited.

Megafil Co.,Ltd.

MG-FM-7.8-001, R00 (01/07/19)

Page 2 of 6

Certificate No. : M1439/24

Procedure Used : European Standard EN12469 : 2000 has the status of British Standard, Biotechnology Performance criteria for microbiological safety cabinets.

: NSF International Standard / American National Standard NSF / ANSI 49-2008 Biosafety Cabinet : Design, Construction, Performance and Field Certification.

: Australian Standard : AS 1807.23-2000 Determination of intensity of radiation from germicidal ultraviolet lamps.

: Manufacturer's specification.

1. Downflow velocity test.

Measurement Information

No. of Rows	No. of Readings	Grid Spacing Front-Back	Grid Spacing Side-Side	Probe height Above sash
2	8	1/4,3/4	1/8,3/8	100mm

Measurement Data. (m/s.)

0.37	0.43	0.41	0.39
0.36	0.35	0.32	0.34

Average velocity 0.37 m/s (73 FPM.) **Velocity range** 0.25-0.50 m/s (49-98 FPM.)

Uniformity(EN: +/-20%avg.) 0.30 - 0.44 m/s (58 - 88 FPM.)

Supply filter dimension 24 x 72 (inch x inch) **Supply filter area** 10.69 SQ.FT

Downflow volume (Q) 780 CFM.

Result Summary ☒ Pass ☐ Fail

Equipment used : Thermo Anemometer **Model** 425 **S/N :** 02968605 **Calibration date :** 10/05/2024

Megafil Co.,Ltd.

MG-FM-7.8-001, R00 (01/07/19)

Page 3 of 6

Certificate No. : M1439/24

2. Inflow velocity test.

Select method. : ☐ DIM ☒ Exhaust velocity. ☐ MFG's Specifications

MGF's Specifications method

0.54	0.57	0.55	0.54	0.55
0.56	0.55	0.56	0.57	0.54
0.59	0.53	0.54	0.57	0.56
0.53	0.6	0.56	0.55	0.58
0.55	0.58	0.54	0.53	0.55

(m/s.)

Average Inflow velocity 0.47 m/s (93 FPM.) **Velocity range** ≥0.40 m/s (≥79 FPM.)

Inflow dimension 8 x 72 (inch x inch) **Inflow area** 4.00 SQ.FT

Inflow volume(Q) 372 CFM

Result Summary ☒ Pass ☐ Fail

Adjustments Required ☐ Fan Speed ☐ Damper

Equipment used : Thermo Anemometer **Model** 425 **S/N :** 02968605 **Calibration date :** 10/05/2024

3. HEPA filter leak test.

Measurement Data

HEPA Filter	PAO Upstream Conc.(calculated)	Specification	Measured leak penetration
Supply HEPA Filter	18 µg/l.	<0.01%	<0.01%
Exhaust HEPA Filter	18 µg/l.	<0.01%	<0.01%

Megafil Co.,Ltd.

MG-FM-7.8-001, R00 (01/07/19)

Page 4 of 6

Certificate No. : M1439/24

Leak location

Supply HEPA Filter
Back



Exhaust HEPA Filter
Back



Result Summary ☒ Pass ☐ Fail

Equipment used : Aerosol Photometer **Model** TDA-2H **S/N :** 20138 **Calibration date :** 08/05/2024

Equipment used : Smoke Generator **Model** TDA-6C **S/N :** 20192

4. Airflow smoke patterns test

Measurement Information

- Downflow Pattern test : Smoke shall be passed from one end of the cabinet to the other, along the centerline of the work surface, at a height of 4 inch (10 cm) above the top of the access opening
- View screen retention test : Smoke shall be passed from one end of the cabinet to the other, 1.0 in (2.5 cm) behind the view screen, at a height 6.0 inch (15 cm) above the top of the access opening.
- Work opening edge retention test : Smoke shall be passed along the entire perimeter of the work opening. Particular attention should be paid to corners and vertical edges.
- Sash/window seal test : Smoke shall be passed up the inside of the window 2 in (5 cm) from the sides and along the top of the work area.

Megafil Co.,Ltd.

MG-FM-7.8-001, R00 (01/07/19)

Certificate No. : M1439/24

Result Summary

Downflow Pattern test	☒ Accept	☐ Non-Conforming
View screen retention test	☒ Accept	☐ Non-Conforming
Work opening edge retention test	☒ Accept	☐ Non-Conforming
Sash/window seal test	☒ Accept	☐ Non-Conforming

5. Site installation

Sash Alarm.	☐ Pass	☐ Fail	☒ N/A
Interlock System.	☐ Pass	☐ Fail	☒ N/A
Exhaust System Performance	☐ Pass	☐ Fail	☒ N/A

Remark / Recommendation

ระบบ Site installation ไม่มีการตรวจสอบ เนื่องจากตู้ไม่มีฟังก์ชันนี้

6. Illumination Test (Lighting) : Option

Lighting should be adequate for safe working within the cabinet. Illumination measured at the work surface.

Lux

585	936	917	514
849	1400	1465	755

Equipment used : Digital Light Meter Model Easy View 31 S/N : 160404993 Calibration date : 08/05/2024

Remark :

Certificate No. : M1439/24

7. Ultraviolet Lamp Test (UV) : Option

Ultraviolet radiation where UV Lamp are fitted, the intensity of radiation at a wavelength of 254 nm.

 Shall be not less than 400 mW/m² when measures at work floor surface.

 mW/m²

630	1450	1480	690
380	920	930	390

Equipment used : UVC LIGHT METER Model UVC-254SD S/N : Q879819 Calibration date : 08/05/2024

Remark :

-000-

Certificate of Calibration

LIQUID BATH


Certificate No.: MC 2314268

Page 1 of 3

 Customer : Water Analysis Center Co., Ltd.
 1/94 Moo 5, T.Kantham, A.U-Thai, Ayutthaya 13210.

Reference Job No. : 23-2833 Received Date : 15 December 2023

Description : Water Bath

Manufacturer : ESSTELL Model : EWB-122D

Serial No. : 20180508122 ID. No. : WWL 0214

Marking : Additionally for the purpose of identification by this laboratory a label marked with this certificate number (MC 2314268) has been attached to the case.

Method : In-House calibration procedure MWL-T-029 this method is reference to ASTM E715 "Liquid Bath".

Location of Calibration : Water Analysis Center Co., Ltd. ; Laboratory.

Environmental Condition : Ambient Temperature : (29.4 to 29.8) °C
 Relative Humidity : (49.0 to 52.0) %

Date of Calibration : 15 December 2023 Date of Issue : 19 December 2023

 Checked by : Chalermkit Rakphada
 Chalermkit Rakphada
 (Calibration Engineer)

 Approved by : Aittipong Karana Kasit
 Aittipong Karana Kasit
 (Technical Manager)

The uncertainties are for a confidence probability of approximately 95%

This certificate is issued in accordance with the conditions of accreditation granted by the National Standardization Council of Thailand-Office of the National Standardization Council that has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realized at the corresponding national standards laboratory. This certificate may not be reproduced other than in full except with the prior written approval of Master Calibration Co.,Ltd.

Certificate No.: MC 2314268

Page 2 of 3

Reference Standard Instrument :

Description	Certificate No.	Serial No.	Due date	Traceable thru
Data Acquisition/Switch Unit	MC 2301270	MY44020009	9 Mar 2024	MCAL

With Thermocouple Type " T " ID. No.27/1 to 27/5

Traceability :

The measurement standard traceable to the international system of units (SI) through certificate as mentioned above


1. Calibration Procedure:

This Instrument was calibration according to ASTM E715 - 2007 by comparison with calibrated sensor under no load condition. The sensor were placed on five points and located one sensor in each of the eight corners of the chamber and was away from the each wall of 5 cm to 10 cm. And placed the five sensor within 2.5 cm of the geometric center of the chamber.

Temperature Uniformity - the maximum difference of measured temperatures at any sensors and the measured temperature at the reference location which are observed at the same time or at as close an observation time as possible to determine the temperature pattern or homogeneity within the chamber under steady state conditions. The reference sensor should preferably be located at the geometric center of the chamber.

Temperature Stability - one-half of the greatest maximum difference of measured temperatures at any one sensor.

Overall Variation - The Difference of the maximum and minimum measured temperatures throughout observation.



- Overall Ambient Temperature around the Chamber variation : 1.3 °C
- Overall Line Voltage variation : 0.0 V
- Chamber Size (W*H*D) : 50 cm x 12 cm x 30 cm
- Water Level : 7 cm

Checked by : Chalermkit

Certificate No.: MC 2314268

Page 3 of 3

2. Result of calibration :

Temperature Measurement Accuracy Test

Indicating Temperature (°C)	Measured Temperature (°C) at Spread Locations					Uncertainty (±°C)
	#1	#2	#3	#4	Ref. #5	
45.0	44.5	44.4	44.5	44.5	44.6	0.45

Chamber Characterization Result

Desired Temperature (°C)	Controller Temperature (°C)	Indicating Temperature (°C)	Temperature Stability (±°C)	Temperature Uniformity (°C)	Overall Variation (°C)
44.5	45.0	45.0	0.62	0.88	1.5

The reported uncertainty of measurement was based on a standard uncertainty multiplied by a coverage factor $k = 2.0$, providing a level of confidence of approximately 95 %.

This certificate will certify of the calibrated equipment only.

End of Certificate

Checked by : Chalermkit

[MCF-Q-077 ; Rev.6 ; Date : 22/04/2021]

Certificate No.: MC 2314270

Page 2 of 3

Reference Standard Instrument :

Description	Certificate No.	Serial No.	Due date	Traceable thru
Data Acquisition/Switch Unit	MC 2214032	MY41029992	26 Dec 2023	MCAL

With Thermocouple Type " T " ID. No.31/1 to 31/9

Traceability :

The measurement standard traceable to the international system of units (SI) through certificate as mentioned above


1. Calibration Procedure:

This Instrument was calibration according to TLAS G-20 by comparison with calibrated thermocouple type T under no load condition. The Thermocouples were placed on nine points and located one thermocouple in each of the eight corners of the chamber and was away from the each wall of 5 cm to 10 cm. And placed the ninth thermocouple within 2.5 cm of the geometric center of the chamber.

Temperature Uniformity - the maximum difference of measured temperatures at any sensors and the measured temperature at the reference location which are observed at the same time or at as close an observation time as possible to determine the temperature pattern or homogeneity within the chamber under steady state conditions. The reference sensor should preferably be located at the geometric center of the chamber.

Temperature Stability - one-half of the greatest maximum difference of measured temperatures at any one sensor.

Overall Variation - The Difference of the maximum and minimum measured temperatures throughout observation.



Overall Ambient Temperature around the Chamber variation : 0.4 °C

Overall Line Voltage variation : 0.0 V


Chamber Size (W*H*D) : 65 cm x 80 cm x 50 cm

Checked by : Chalermkit

[MCF-Q-077 ; Rev.6 ; Date : 22/04/2021]

Certificate of Calibration

TEMPERATURE
CONTROLLER ENCLOSURES



Certificate No.: MC 2314270

Page 1 of 3

Customer : Water Analysis Center Co., Ltd.
1/94 Moo 5, T.Kantham, A.U-Thai, Ayutthaya 13210.

Reference Job No. : 23-2833 Received Date : 15 December 2023
Description : Incubator
Manufacturer : Memmert Model : IN260
Serial No. : D619.0170 ID. No. : WWL 0192
Marking : Additionally for the purpose of identification by this laboratory a label marked with this certificate number (MC 2314270) has been attached to the case.
Method : In-House calibration procedure MWI-T-033 this method is reference to TLAS G-20 "Temperature Controlled Enclosures".
Location of Calibration : Water Analysis Center Co., Ltd. ; Laboratory.
Environmental Conditions : Ambient Temperature : (25.2 to 25.6) °C
Relative Humidity : (65.4 to 66.2) %
Date of Calibration : 15 December 2023 Date of Issue : 19 December 2023

Checked by : Chalermkit
Chalermkit Rakphada
(Calibration Engineer)

Approved by : Aittipong
Aittipong Kanchanasit
(Technical Manager)

The uncertainties are for a confidence probability of approximately 95%

This certificate is issued in accordance with the conditions of accreditation granted by the National Standardization Council of Thailand-Office of the National Standardization Council that has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realized at the corresponding national standards laboratory. This certificate may not be reproduced other than in full except with the prior written approval of Master Calibration Co.,Ltd.

[MCF-Q-077 ; Rev.6 ; Date : 22/04/2021]

Certificate No.: MC 2314270

Page 3 of 3

2. Result of calibration :

Temperature Measurement Accuracy Test

Indicating Temperature (°C)	Measured Temperature (°C) at Spread Locations									Uncertainty (±°C)
	#1	#2	#3	#4	#5	#6	#7	#8	Ref. #9	
35.0	35.2	35.2	35.2	35.2	35.1	35.1	35.0	35.1	35.1	0.44

Chamber Characterization Result

Desired Temperature (°C)	Controller Temperature (°C)	Indicating Temperature (°C)	Temperature Stability (±°C)	Temperature Uniformity (°C)	Overall Variation (°C)
35.0	35.0	35.0	0.13	0.21	0.4

The reported uncertainty of measurement was based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95 %.

This certificate will certify of the calibrated equipment only.

End of Certificate

Checked by : Chalermkit

[MCF-Q-077 ; Rev.6 ; Date : 22/04/2021]

Certificate of Calibration

AUTOCLAVE



Certificate No.: MC 2314269

Page 1 of 3



Customer : Water Analysis Center Co., Ltd.
1/94 Moo 5, T.Kantham, A.U-Thai, Ayutthaya 13210.

Reference Job No. : 23-2833 Received Date : 15 December 2023
Description : Autoclave
Manufacturer : TOMY Model : Autoclave ES-315
Serial No. : 51135128 ID. No. : WWL 0083
Marking : Additionally for the purpose of identification by this laboratory a label marked with this certificate number (MC 2314269) has been attached to the case.
Method : In-House calibration procedure MWI-T-036 this method is reference to based on BS 2646 : 1993 Part 5 "Autoclave".
Location of Calibration : Water Analysis Center Co., Ltd. ; Laboratory.
Environmental Condition : Ambient Temperature : (29.4 to 30.7) °C
Relative Humidity : (50.0 to 52.0) %
Date of Calibration : 15 December 2023 Date of Issue : 19 December 2023

Checked by : Chalermit
Chalermkit Rakphada
(Calibration Engineer)

Approved by : Aittipong
Aittipong Kanjanasit
(Technical Manager)

The uncertainties are for a confidence probability of approximately 95%

This certificate is issued in accordance with the conditions of accreditation granted by the National Standardization Council of Thailand-Office of the National Standardization Council that has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realized at the corresponding national standards laboratory. This certificate may not be reproduced other than in full except with the prior written approval of Master Calibration Co.,Ltd.

[MCF-Q-077 ; Rev.6 ; Date : 22/04/2021]

Certificate No.: MC 2314269

Page 2 of 3

Reference Standard Instrument :

Description	Certificate No.	Serial No.	Due date	Traceable thru
Temperature Recorder RTD 100 Ohm	MC 2300163	M79252	9 Jan 2024	MCAL
Temperature Recorder RTD 100 Ohm	MC 2300164	5978194	9 Jan 2024	MCAL
Temperature Recorder RTD 100 Ohm	MC 2300165	M79251	9 Jan 2024	MCAL

Traceability :


The measurement standard traceable to the international system of units (SI) through certificate as mentioned above

1. Calibration Procedure:

The equipment list above was calibrated an accuracy of temperature in a chamber of the sterilizer.

The calibration was performed by direct measurement of generated temperatures using the standard thermometer with three temperature sensors. The data was recorded in a period of fifteen minutes of the sterilizing status. The temperature scale used was based on ITS-90.

The calibration of sterilizer was carried out at the point indicated by following the In-house calibration method No. MWI-T-036 based on BS 2646 : 1993 : Part 5 in Tests for performance section.



- Overall Line Voltage variation : 0.0 V

Checked by : Chalermit

[MCF-Q-077 ; Rev.6 ; Date : 22/04/2021]

Certificate No.: MC 2314269

Page 3 of 3

2. Result of calibration :

Temperature Measurement Accuracy Test

Indicating Temperature (°C)	Measured Temperature (°C) at Spread Locations			Uncertainty (±°C)
	#1	#2	#3	
121	121.72	121.73	121.95	0.61

Characterization Result

Desired Temperature (°C)	Setting Temperature (°C)	Timer Setting (min)	Indicating Temperature (°C)	Indicating Pressure (kPa)	Measured Stability (±°C)	Measured Uniformity (°C)	Overall Variation (°C)
121	121	15.0	121	120	0.60	0.35	1.35

The reported uncertainty of measurement was based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95 %.

This certificate will certify of the calibrated equipment only.

End of Certificate

Checked by : Chalermit

[MCF-Q-077 ; Rev.6 ; Date : 22/04/2021]